

FEB 28 1994

RC 1221

L127004PA577

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE COUNTY Located In: Corner Code #
1. Public Land Survey T 1 S R 9 E C-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12/3/93 WCD
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on OCTOBER 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (7, C) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
WPA (1930's): "IRON NW-20"
LCRC (1973): "FOUND 1/2" BAR IN MONUMENT BOX" (RC-220; L. 18396, P. 325)

Vertical stamp: RECEIVED - 3 PM 12/11/93

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN RC-220 AS FOLLOWS:

- N 44°-57' E. 71.20'; PK NAIL IN POLE (MEAS. N 48° E, 71.28')
S 31°-29' E. 95.05'; PK NAIL IN POLE (NOT FOUND)
S 44°-19' W. 77.00'; PK NAIL IN POLE (MEAS. S 46° W, 67.49')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" IRON BAR IN MONUMENT BOX IN INTERSECTION OF FIVE MILE ROAD AND NEWBURGH ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" ON POINT.

- N. 48° W. 65.46'; CUT CHISELED "X" IN SOUTHEAST BOLT OF STREET LIGHT BASE.
N. 48° E. 71.28'; FOUND PK NAIL WITH "WCRC" TAG IN SOUTHEAST SIDE OF UTILITY POLE.
S. 55° E. 76.51'; CUT CHISELED "X" IN NORTHWEST BOLT OF STREET LIGHT BASE.
S. 46° W. 67.49'; FOUND PK NAIL WITH "WCRC" TAG IN NORTHWEST SIDE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
Surveyor's Michigan License No. 26467