

10001022

SURVEY A  
RF

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 28 2000

For corners in

SECTION

WAYNE  
(County)

Located in: CITY OF LIVONIA Corner Code # C-10

1. Public Land Survey T 1S R 9E \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Liber-30814 Page-1  
99586924 12/21/1999  
F.E. Youngblood, Wayne Co. Register of Deeds

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-8-99 *[Signature]*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on NOV 01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NOTE: NUMBERS IN (\*) ARE USED TO TRACE THE CHAIN OF EVENTS AS RECORDED BY PREVIOUS SURVEYORS WITNESSES

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GOVERNMENT LAND OFFICE (1816) SET 1/4 POST 1930'S WAYNE COUNTY BUREAU OF TAXATION WITNESSES;  
W. OAK 16" N 66° E .13 CHAINS (1) (GONE) MONUMENT (3)  
W. OAK 9" S 87°W .12 CHAINS (2) (GONE) N.E. 89.27 30" MAPLE (4) (GONE)  
S.E. 46.70 MONUMENT (5) (GONE)  
S.E. 55.72 18" CHERRY (6) (GONE)

SHOWN ON PLAT OF "WOODLANDS VILLAGE", RECORDED IN LIBER 69, PAGE 3 (1941)  
SHOWN ON PLAT OF "CURRIE COURT INDUSTRIAL SUBDIVISION", RECORDED IN LIBER 96, PAGES 71, W.C.R. (1976)

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MONUMENT BOX AT THE INTERSECTION OF NEWBURGH AND AMRHEIN ROADS. I VERIFIED IT POSITION BY THE COMPARISON OF THE 1930 REMONUMENTATION EFFORT TO 1999 FIELD MEASUREMENTS. WE ALSO USED AN EXISTING FIRE HYDRANT (10) TO TIE THIS POSITION INTO 1979 INFORMATION.

- \* D-10 TO C-10: 2646.05 RECORDED VERSUS 2646.56 MEASURED.
- \* C-11 TO C-10: 2641.68 RECORDED VERSUS 2641.17 MEASURED
- \* THE ANGLE OF D-10 - C-10 - C-11 IS 89°57'20" RECORDED VERSUS 89°58'04" MEASURED.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 FOUND 1/2" RE-ROD IN MONUMENT BOX, ROAD SURFACE IS ASPHALT.  
SET REMONUMENTATION DISC AND PLASTIC CAP ON IRON  
N 55° E 65.05' SET NAIL AND REMON. TAG IN N. SIDE UTIL. POLE (13) (RECORDED AS 63.50' TO FACE )  
S 45° E 61.79' SET NAIL AND REMON. TAG IN S.W. SIDE UTIL. POLE  
S 56° W 64.41' SET NAIL AND REMON. TAG IN N. SIDE POWER POLE  
S 63° W 77.65' TOP CENTER NUT ON HYDRANT (10) (RECORDED AS 77.48)  
S 63° W 89.79' FD. NAIL AND TAG IN GUY POLE  
N 66° W 82.40' SET NAIL AND REMON. TAG IN S.W. SIDE UTIL. POLE

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *[Signature]*  
Surveyor's Michigan License No. 24618

Date 12-15-1999

R LCR 12 4R 2 Pgs. A *[Signature]*

SECTION "A" CONTINUED

SHOWN ON "NEWBURGH INDUSTRIAL SUBDIVISION" AS RECORDED IN LIBER 101, PAGE 12, WAYNE COUNTY RECORDS (1985)  
SHOWN ON "NEWBURGH ESTATES SUBDIVISION" AS RECORDED IN LIBER 68, PAGE 45, WAYNE COUNTY RECORDS (1941)

RECORDED ON ACT 74 (1972) BY SURVEYOR FRANCIS A PAPKE (RC 124)

FOUND MONUMENT (3) IN MONUMENT BOX (7)  
N.N.E. 82.03' P.K. NAIL IN D.E. POLE (8) (GONE)  
S.E. 65.00 P.K. NAIL IN D.E. POLE (9) (GONE)  
S.W. 77.48 TOP NUT ON HYDRANT (10)  
N.W. 64.62 P.K. NAIL IN D.E. POLE (11)

RECORDED ON ACT 74 (1979) BY SURVEYOR JOHN J. McMAHON (RC 694)

FOUND IRON (12) IN MONUMENT BOX (7)  
N.E. 63.50 FACE OF WOOD POLE (13)  
S.E. 65.00 P.K. NAIL ON WOOD POLE (9) (GONE)  
N.W. 64.80 NAIL IN WOOD POLE (11) (GONE)

SURVEY &  
RECORDS SECTION

FEB 28 2000

SECTION