

FEB 20 1994

RC 1222

COMING

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

L127004PA578

For corners in WAYNE COUNTY Located In: Corner Code #
1. Public Land Survey T 1 S R 9 E C-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12/31/93 WCD
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (11, B) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
WPA (1930's): "MON NW-32"
LCRC (1972): "1/2" PIPE IN MON. BOX AT NEWBURGH ROAD (RC-115; L. 18145, P. 207)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX; ALL WITNESSES SHOWN IN RC-115 HAVE BEEN DESTROYED; CHECKED DISTANCE TO CORNER C-12; WAYNE COUNTY SECTION MAPS SHOW DISTANCE TO BE 2633.76' AND 2633.96' (AVERAGE EQUALS 2633.86'), MEASUREMENT ON 11/23/93 EQUALS 2634.05'. ACCEPTED LOCATION AS FOUND.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1" IRON PIPE) IN MONUMENT BOX IN NEWBURGH SOUTH OF E. N. HINES DRIVE; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" OVER PIPE OF MONUMENT.

- N. 70° W. 57.42'; CENTERLINE OF NORTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
S. 89° E. 49.72'; CUT CHISELED "X" IN WEST RIM OF MBT MANHOLE.
S. 22° E. 109.28'; CUT CHISELED "X" IN WEST RIM OF STORM SEWER MANHOLE.
S. 34° W. 82.26'; FOUND PK NAIL WITH TAG NO. 10705 IN NORTHWEST FACE OF UTILITY POLE.
S. 55° W. 65.57'; SET NAIL WITH "WCR WITNESS" TAG IN SOUTHWEST FACE OF 12" BIRCH TREE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
Surveyor's Michigan License No. 26467

93 DEC -3 PM 12:11
FOR SETTING MONUMENTS
11/23/93
M