

SURVEY & REMONUMENTATION
FILE DO NOT MAIL
MAR 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corner **SECTION**

| WAYNE (County) | Located In: CITY OF LIVONIA | Corner Code # |
|---------------------------------------|--------------------------------|---------------|
| 1. Public Land Survey | T 1S R 9E | C-12 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-8-97
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on NOV 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GOVERNMENT LAND OFFICE (1830'S) SET 1/4 POST
- W. OAK 10° N 65° W 1.05 CHAINS (1) (GONE)
- W. OAK 11° N 04° E .85 CHAINS (2) (GONE)
- 1930'S WAYNE COUNTY BUREAU OF TAXATION WITNESSES;
- CROSS IN STONE
- N.N.E. 64.82' 6" PEAR (3) (GONE) WEST 32.83' MON. (3) (GONE)
- N.E. 59.80' 6" APPLE (4) (GONE)
- S.E. 41.40' 24" MAPLE (5) (GONE)
- SOUTH 53.00' NON-LABELLED WITNESS (6) (GONE)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR IN A MONUMENT BOX PER PREVIOUS WITNESSES. I VERIFIED ITS POSITION BY THE FOLLOWING MEASUREMENTS TO THE 1930'S WAYNE COUNTY RE-SURVEY EFFORT:
C-12 TO C-13 MEASURED 2656.05' VERSUS 2655.71" RECORDED
C-12 TO B-12 MEASURED 2631.77' VERSUS 2631.36' RECORDED
ANGLE BETWEEN B12-C12-C13 MEASURED AT 92°29'02" VERSUS 92°28'37" RECORDED \$10.00 DEED
THESE MEASUREMENTS WERE OBTAINED BY TRAVERSING THE S.E. 1/4 OF SAID SECTION 31, FOREST E. YOUNGBLOOD, REGISTER OF DEED WAYNE COUNTY, MI
Receipt #43171

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1/2" REBAR IN A WAYNE COUNTY MONUMENT BOX (7) IN THE CENTERLINE OF NEWBURGH ROAD. I SET A WAYNE COUNTY REMONUMENTATION TAG AND PLASTIC CAP ON THIS BAR.
S 89°E 47.79 SET NAIL & REMON TAG IN S. SIDE OF UTILITY POLE
S 89°E 59.95 FOUND 1/2" RECENT REBAR AT PROPERTY CORNER
S 26°E 110.53 SET NAIL & REMON TAG IN S.W. SIDE OF UTILITY POLE
S 27°W 88.85 TOP NUT OF HYDRANT
N 84°W 32.42 SET NAIL & REMON TAG IN N. SIDE OF UTILITY POLE (9)
N 60°W 124.47 S.E. CORNER OF BRICK HOUSE AT #9411

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date 12-16-1997

D-1 CR-10-4R-7 PL-11

RECORDED ACT 74 - LIBER 18145, PAGE 205, W.C.R. (1972) WHICH STATES:

FOUND 1/2" PIN IN MONUMENT BOX WHICH AGREES WITH DISTANCES RECORDED IN PLATS AND TAX DESCRIPTIONS.

1/2" PIN IN MON. BOX AT NEWBURG ROAD (7)
POWER POLE WITH NAIL & TAG M.S.H.D. S 85°E 29.74' (8) (GONE)
TEL. POLE WITH NAIL & TAG M.S.H.D. N 85°W 32.23' (9) (MEAS 32.42' TO C/L POLE)
11" BOX ELDER NAIL & TAG M.S.H.D. N 25°W 61.59' (10) (GONE)
(NOTE: SKETCH ON BACK OF ACT 74 SHOWS NEWBURG ROAD RUNNING NORTH AND SOUTH CENTERED ON THIS CORNER)

C-12 IS SHOWN ON THE PLAT OF "SUPERVISOR'S LIVONIA PLAT NO. 12" RECORDED IN LIBER 66, PAGE 65. (1938)

C-12 IS SHOWN ON THE PLAT OF "HORTON'S SUBDIVISION" PRIOR TO ITS REPLATTING AS SAID "SUPERVISOR'S LIVONIA PLAT NO. 12".

THIS POSITION HAS BEEN RECENTLY RE-WITNESSED BY MR. KEN WILKERSON OF ORCHARD, HILTZ, AND McCLIMENT.

SURVEY &
REMONUMENTATION

MAR 17 1998

SECTION

4972-200-112

8-10-98