

SURVEY & REMONUMENTATION

RC 1474

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING
 22 FEB 94 3:39 P.M. RECEIPT# 930
 RECORDED
 FOREST E. YOUNGLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

L127796PA702

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-12-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

For corners in
WAYNE COUNTY
 (County)

Located In: Corner Code #

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>C - 13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		R		
	S		R		
3. Miscellaneous Property in Sec.	S		R		
	S		R		

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RC 1474

I, **ROBERT J. SMALLEY**, in a field survey on **SEPTEMBER 29**, 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POPLAR 9" DIAMETER COR. TREE"
- WPA SURVEY (1930'S) "FOUND 3/4" IRON PIPE, REPLACED WITH 4'0" CONCRETE MONUMENT"
- LCRC (1975): "FOUND IRON IN MONUMENT BOX" (RC 445; L. 19252, P. 899)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND NEWBURGH ROAD. CHECKED DISTANCES TO C-12 AND D-1 (WESTLAND) AGAINST DISTANCES MEASURED BY WPA SURVEY AND COMPARED ANGLE AT CORNER TO ANGLE SHOWN IN SUPERVISOR'S LIVONIA PLAT NO. 12 (L. 66, P. 65) AS FOLLOWS:

C-13 TO C-12	NORTH	2655.60'	(MEAS. 2655.90')
C-13 TO D-1(WESTLAND)	S 87°50'10"E	2633.02	(MEAS. 2633.66')
ANGLE AT CORNER (C-12 , C-13 , D-13)	92°10'07"/PLAT	(MEAS. 92°10'07")	

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" BAR IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND NEWBURGH ROAD (CONCRETE PAVEMENT); SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER 1/2" BAR.

- N. 41° E. 77.01'; SET NAIL AND "WCR WITNESS" TAG IN NW FACE OF UTILITY POLE.
- S. 43° E. 74.04'; SET NAIL AND "WCR WITNESS" TAG IN SW FACE OF UTILITY POLE.
- S. 59° W. 91.30'; SET NAIL AND "WCR WITNESS" TAG IN NW FACE OF UTILITY POLE.
- N. 52° W. 82.86'; SET NAIL AND "WCR WITNESS" TAG IN SW FACE OF UTILITY POLE.

ZR
11-D-MISC.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

