

\$ 4.00 REMONUMENTATION
 \$ 10.00 DEED
 23 DEC 96 11:12 A.M. RECEI
 RECORDED
 WEST E. YOUNGBLOOD, REGISTER
 WAYNE COUNTY, MI EDS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
 (County)

Located in: Corner Code #
 CITY OF LIVONIA E-11

1. Public Land Survey

T 1S R 9E

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 12-16-1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	10	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, PAUL V. SCHWINNER, in a field survey on NOV 11, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.D. (1816) POST AT DIST OF 80 CHAINS G
 BEECH 12° S 21° E 10 LINKS (GONE)
 BEECH 9° S 63° E 20 LINKS (GONE) G

1930'S BUREAU OF TAXATION - FOUND IRON
 NW 52.19' EDISON POLE (GONE) SW 53.78' 30' OAK (GONE)
 NE 45.77' 10' ELM (GONE) SE 42.12' EDISON POLE (GONE)
 1956 - SHOWN ON PLAT OF 'COUNTRY HOMES SUB. No. 1', LIBER 76, PG 71

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND A 1" IRON PIPE IN A MONUMENT BOX IN ASPHALT ROAD AT THE INTERSECTION OF PLYMOUTH ROAD AND YALE AVENUE TO THE SOUTH. CHECKED CORNER WITNESSES AS SHOWN IN R.C. 885 (LIBER 84, PG 7-8) AND DISTANCES TO D-11 AND F-11 AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:

N 40° W 57.86 (57.84 MEAS) N.E. BOLT IN BASE OF LIGHT POLE
 N 00° E 29.97 (29.97 MEAS) BACK OF 6" CONC. CURB E. & W.
 S 45° E 69.76 (69.74 MEAS) S.W. BOLT IN BASE OF LIGHT POLE
 S 35° W 73.19 (73.16 MEAS) BACK OF WALKS TO S. & W. POLE
 E-11 TO D-11 N 89°56'30" W 2647.06 RECORD 2647.27 MEASURED
 E-11 TO F-11 S 89°54'10" W 2634.24 RECORD 2634.67 MEASURED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET 'WAYNE COUNTY REMONUMENTATION' TAG AND CAP No. 24618 ON FOUND 1" IRON IN MONUMENT BOX AT THE INTERSECTION OF PLYMOUTH ROAD AND YALE AVENUE TO THE SOUTH.

N 00° E 29.97 BACK OF 6" CONC. CURB E. & W.
 N 40° E 67.54 NAIL AND "WCR WITNESS TAG" IN WEST SIDE EDISON POLE
 S 45° E 69.70 S.W. BOLT IN BASE OF LIGHT POLE
 S 35° E 70.46 NAIL AND "WCR WITNESS TAG" IN S.W. SIDE EDISON POLE
 S 35° W 73.16 INTERSECTION OF THE BACK OF WALKS RUNNING TO THE S. & W.
 N 40° W 57.84 N.E. BOLT IN BASE OF LIGHT POLE

THE SELECTED LOCATION AS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY THE PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer
 Surveyor's Michigan License No. 24618

Date 11-23-96

4k
 10l
 P.V.

SECTION A (CONT)

1959 - SHOWN ON PLAT OF 'YALE HOMES SUB No.2', LIBER 84, PG 7-8
1987 - SHOWN ON PLAT OF 'BELDEN INDUSTRIAL PARK ', LIBER 101, PG 99-100

RECORDATION CERTIFICATE 885, RECORDED IN LIBER 23100, PG 252 (1987)

FOUND 1' IRON IN HANDHOLE

N 40° W 57.86 (57.84 MEAS) N.E. BOLT IN BASE OF LIGHT POLE

N 00° E 29.98 (29.97 MEAS) BACK OF 6' CONC. CURB E. & W.

S 45° E 69.76 (69.74 MEAS) S.W. BOLT IN BASE OF LIGHT POLE

S 35° W 73.19 (73.16 MEAS) BACK OF WALKS TO S. & W. POLE

1989 - SHOWN ON PLAT OF 'LEVAN COURT SUBDIVISION'

FILE DO NOT REMOVE