

SURVEY & REMONUMENTATION

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE
 Filing requirement of Act 74, Mich. P.A. 1970

\$ 4.00 REMONUMENTATION
 \$ 7.00 DEED

RECEIVED
 APR 05 11:21 A.M.
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER
 WAYNE COUNTY, MI

LIBER 28465 PAGE 789

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-13-95
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

For corners in
WAYNE COUNTY
 (County)

Located In: **LIVONIA** Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|---------------|
| 1. Public Land Survey | T | <u>1 S</u> | R | <u>9 E</u> | <u>E - 13</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **ROBERT J. SMALLEY**, in a field survey on **MARCH 23, 1995**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA SURVEY (1930'S) "FOUND IRON & REPLACED WITH MONUMENT"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR IN MONUMENT BOX IN JOY ROAD (ASPHALT PAVEMENT) - CHECKED DISTANCE TO D-13 AND WITNESS MONUMENTS AGAINST DISTANCES MEASURED BY WPA SURVEY AS FOLLOWS:

D-13 to E-13 -	N 87°50'10" W, 2650.07'(CALC.)	(MEAS. 2650.63')
E-13 to WITNESS -	NORTH 33.00'	(MEAS. 32.95')
E-13 to WITNESS -	N 43° E 46.70'	(MEAS. 46.70')
E-13 to WITNESS -	N 70° E 97.73'	(MEAS. 98.18')

NOTE: THIS CORNER IS NOT COMMON WITH CORNER E-13 OF WESTLAND, T. 2 S., R. 9 E.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT IN MONUMENT BOX IN JOY ROAD (ASPHALT PAVEMENT); SET "WAYNE COUNTY REMONUMENTATION" TAG & SURVEY CAP NO. "30086-26467" OVER IRON BAR.

NORTH 32.95'; FOUND CONCRETE MONUMENT.
 N. 43° E. 46.70'; FOUND CONCRETE MONUMENT.
 N. 70° E. 98.18'; FOUND CONCRETE MONUMENT.
 S. 53° E. 77.72'; CENTER LINE OF WORKING NUT ON FIRE HYDRANT

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date Dec. 13, 1995
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467



95268805

4R
7D
DJD