

\$ 4.00 REMONUMENTATION  
 \$ 10.00 DEED  
 23 DEC 96 11:12 A.M. RECEI A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER EDG  
 WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE  
 (County)

Located In: CITY OF LIVONIA Corner Code #

1. Public Land Survey	T	1SR	9E	F-11
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Compliance with ACT 345, P.A. 1990 *D.B.J.*  
 APPROVED ON: 12-16-1996  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on NOV 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6	5		4		3		2			1
3												
4		7	8		9		10		11			12
5												
6		18	17		16		15		14			13
7												
8		19	20		21		22		23			24
9												
10		30	29		28		27		26			25
11												
12		31	32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.D. (1816) POST AT AVERAGE DIST OF 40 CHAINS BETWEEN SECTION CORNERS  
 W. ASH 10° S 44°E 19 LINKS (GONE)  
 BEECH 16° S 24°E 31 LINK (GONE)
  - 1930'S BUREAU OF TAXATION - FOUND IRON  
 NW 37.42' EDISON POLE (GONE) NE 80.43' 14' PEAR (GONE)  
 NE 144.15' 26' ELM (GONE) SW 37.42' EDISON POLE (GONE)  
 SE 102.68' TELE POLE (GONE)
  - 1935 - SHOWN ON PLAT OF SUPERVISOR'S LIVONIA PLAT No. 1, LIBER 65, PG 52
- (CONTINUED ON BACK)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 5/8" IRON PIPE IN MONUMENT BOX SET IN ASPHALT AT THE INTERSECTION OF PLYMOUTH ROAD AND STARK ROAD. CHECKED REMAINING CORNER WITNESSES SHOWN ON R.C. 700, AND R.C. 1084 AND DISTANCES TO F-12 AND E-11 AGAINST DISTANCES MEASURED BY WPA SURVEY OF THE 1930'S AS FOLLOWS:
- R.C. 700 N.W. 63.00 P.K. NAIL IN S.E. SIDE EDISON POLE (MEAS 63.79)  
 N.E. 66.55 P.K. NAIL IN S.E. SIDE TRAFFIC LIGHT POLE (MEAS 66.39)
- R.C. 1084 S 43° W 56.60 NAIL & TAG IN NW FACE OF UTILITY POLE (MEAS 56.57)  
 N 43° W 63.00 NAIL & TAG IN SE FACE OF UTILITY POLE (MEAS 63.79)  
 N 47° E 66.97 NAIL & TAG IN NW FACE OF UTILITY POLE (MEAS 66.39 TO NAIL IN S.W. SIDE)  
 N 28° E 80.40 S.W. BOLT OF LIGHT POLE BASE (MEAS 80.51')
- F-11 TO E-11 S 89°56'30" W 2647.06 RECORD 2647.27 MEASURED
- F-11 TO F-12 S 00°12'05" W 2665.16 RECORD 2665.69 MEASURED
- F-12 IS MISSING AND WAS TEMPORARY RECREATED FROM ADJOINING SUBDIVISION MONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- FOUND 5/8" IRON IN MONUMENT BOX AT INTERSECTION OF PLYMOUTH ROAD AND STARK ROAD. SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP No. 24618 IN FOUND IRON.
  - N 28° E 80.51 S.W. BOLT IN LIGHT POLE BASE
  - N 47° E 66.39 SET NAIL AND "WCR WITNESS" TAG IN N.W. SIDE OF TRAFFIC SIGNAL POLE
  - S 34° E 71.87 INTERSECTION OF BACK OF CONCRETE WALKS
  - S 31° E 70.82 FOUND P.K. NAIL IN CONCRETE WALK
  - S 36° W 56.57 SET NAIL AND "WCR WITNESS" TAG IN S.E. SIDE OF UTILITY POLE
  - S 60° W 75.79 S.E. BOLT OF LIGHT POLE
  - N 59° W 63.79 SET NAIL AND "WCR WITNESS" TAG IN S.W. SIDE OF UTILITY POLE
- THE SELECTED LOCATION AS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY THE PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer  
 Surveyor's Michigan License No. 24618

Date 11-23-96 *J.R.*  
*100*  
*D.B.J.*

SECTION A (CON'T)

1940 - SHOWN ON PLAT OF 'WALTER DANN SUBDIVISION', LIBER 67, PG 79  
1972 - CERTIFICATE OF SURVEY #651, RECORDED IN LIBER 18461, PG 138  
WITNESSES DESCRIBED AS 'IRON IN MONUMENT BOX LOCATED IN  
CENTERLINE OF PLYMOUTH & WAYNE ROADS'

RECORDATION CERTIFICATE 700, RECORDED IN LIBER 20600, PG 818 (1979)  
FOUND 5/8" IRON IN HANDHOLE  
N.W. 63.00 P.K. NAIL IN S.E. SIDE EDISON POLE (MEAS 63.79)  
N.E. 66.55 P.K. NAIL IN S.E. SIDE TRAFFIC LIGHT POLE (MEAS 66.39)  
S.W. 47.67 P.K. NAIL IN N. SIDE TRAFFIC LIGHT POLE (GONE)

1987 - SHOWN ON PLAT OF 'BELDEN INDUSTRIAL PARK ', LIBER 101, PG 99-100

RECORDATION CERTIFICATE 1084, RECORDED IN LIBER 26766, PG 285 (1993)  
FOUND 5/8" IRON IN HANDHOLE  
S 43° W 56.60 NAIL & TAG IN NW FACE OF UTILITY POLE (MEAS 56.57)  
N 43° W 63.00 NAIL & TAG IN SE FACE OF UTILITY POLE (MEAS 63.79)  
N 47° E 66.97 NAIL & TAG IN NW FACE OF UTILITY POLE (MEAS 66.39 TO NAIL IN S.W. SIDE)  
N 28° E 80.40 S.W. BOLT OF LIGHT POLE BASE (MEAS 80.51)

1989 - SHOWN ON PLAT OF 'LEVAN COURT SUBDIVISION'

FILE DO NOT REMOVE