

SUBMITTED
REMONUMENTATION

RC 1223

FEB 28 1993

L127004PA579

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

COMMISSIONER

For corners in

WAYNE COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>G-1</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		R		
	S		R		
3. Miscellaneous Property in Sec.	S		R		
	S		R		

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12/3/93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
WPA (1930's): "MON NW-3"
LCRC (1978): "FOUND MONUMENT IN HANDHOLE" (RC-596; L. 20174, P. 850)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN RC-596 AS FOLLOWS:

N.W., 59.50'; BOLT, CENTERLINE OF HYDRANT (MEAS. N 32° W, 59.47')
S.E., 74.50'; BOLT, CENTERLINE OF HYDRANT (MEAS. S 45° E, 74.04')
S.W., 59.22'; CENTERLINE N.E. BOLT LIGHT POLE (MEAS. S 25° W, 59.09')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT IN MONUMENT BOX WEST OF INTERSECTION OF EIGHT MILE ROAD AND FARMINGTON ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" OVER BAR IN MONUMENT.

N. 32° W. 59.47'; CENTERLINE OF TOP BOLT ON FIRE HYDRANT.
N. 44° E. 86.94'; CENTERLINE OF SOUTHWEST BOLT ON LIGHT POLE BASE.
S. 89° E. 59.47'; FOUND CONCRETE MONUMENT IN MONUMENT BOX, CORNER G-13, T 1 N, R 9 E.
S. 45° W. 74.04'; CENTERLINE OF TOP BOLT ON FIRE HYDRANT.
S. 25° W. 59.09'; CENTERLINE OF NORTHEAST BOLT ON LIGHT POLE BASE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by

Robert J. Smalley

ROBERT J. SMALLEY

Date

Nov. 30 1993

Surveyor's Michigan License No. 26467

RECORDED
INDEXED
DEC 3 1993
PHILIP
M