

FEB 28 1994

LI27004PA581

RC 1225

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE COUNTY Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 1 S R 9 E G-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12/3/93 ACCL
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3				●									
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
- WPA (1930's): "IRON NW-10"
- LCRC (1972): "MONUMENT FOUND IN BOX" (RC-149; L. 18256, P. 77)
- SURVEY (1979): "FD 3/4" IRON IN MON. BOX" (CS-1583; L. 20546, P. 664)
- LCRC (1981): "IRON FOUND IN MON. BOX" (RC-748; L. 21061, P. 911)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON PIPE IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN RC-149 AS FOLLOWS:

- N 50° W, 86.05'; CROSS ON SE COR CONC BASE OF ORN. LT. (MEAS. N 49° W, 86.02')
- N 45° E, 70.59'; CROSS ON SW COR CONC BASE OF ORN. LT. (CROSS NOT FOUND, 70.85' TO BOLT)
- S 45° E, 72.88'; CROSS ON NW COR CONC BASE OF ORN. LT. (LIGHT HAS BEEN MOVED)
- S 30° W, 68.80'; CROSS ON NE COR CONC BASE OF ORN. LT. (LIGHT HAS BEEN MOVED)

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" IRON PIPE IN MONUMENT BOX IN INTERSECTION OF SEVEN MILE ROAD AND FARMINGTON ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" OVER PIPE.

- N. 50° W. 86.02'; FOUND CUT CROSS IN SOUTH SIDE OF CONCRETE LIGHT POLE BASE.
- N. 39° E. 70.85'; CENTERLINE OF SOUTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
- S. 45° E. 68.67'; CENTERLINE OF NORTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
- S. 31° W. 69.17'; CENTERLINE OF NORTHEAST BOLT ON CONCRETE LIGHT POLE BASE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
ROBERT J. SMALLEY
Surveyor's Michigan License No. 26467

NOV 30 1993
 RC-149
 2R
 110
 M