

FEB 29 1994

RC 1226

LI27004PA582

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 9 E G-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/3/93 JCR
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

A B C D E F G H I J K L M

Grid table with 13 rows and 13 columns (A-M). Cell (10, G) contains a black dot.

I, ROBERT J. SMALLEY, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
WPA(1930's): "5 NAILS W-27"
LCRC (1974): "G-10 - CORNER OBLITERATED, BUT REFERENCED BY TWO MONUMENTS SET BY WAYNE COUNTY ROAD COMMISSION AT 500.00 FT. NORTH AND 500.00 FT. SOUTH OF THE CORNER ON THE WEST SEC. LINE." (RC-345; L. 18886, P. 529)
LCRC (1990): "G-10 (A), FIP IN MONUMENT BOX 500' NORTH OF OBLITERATED WEST 1/4 CORNER, SECTION 27" G-10 (B), FOUND MONUMENT IN MONUMENT BOX 500' SOUTH OF OBLITERATED WEST 1/4 CORNER, SECTION 27" (RC-982; L. 24840, P. 958)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-10 (A): FOUND 1/2" IRON PIPE IN MONUMENT BOX, 500' NORTH OF OBLITERATED CORNER G-10; CHECKED WITNESSES RECORDED IN RC-982 AS FOLLOWS:
Az 47°, 85.91'; CENTERLINE OF SW BOLT OF LIGHT POLE BASE. (MEAS. N 47° E, 85.93')
Az 136°, 93.56'; CENTERLINE OF NW BOLT OF LIGHT POLE BASE. (MEAS. S 45° E, 93.50')
Az 219°, 64.60'; CENTERLINE OF SE BOLT OF LIGHT POLE BASE. (MEAS. S 39° W, 64.59')
Az 331°, 83.74'; CENTERLINE OF SE BOLT OF LIGHT POLE BASE. (MEAS. N 29° W, 83.69')
G-10 (B): FOUND MONUMENT (WITH 1/2" IRON) IN MONUMENT BOX, 500' SOUTH OF OBLITERATED CORNER AT G-10, CHECKED WITNESSES RECORDED IN RC-982 AS FOLLOWS:
Az 33°, 120.83'; CENTERLINE OF NW BOLT OF LIGHT POLE BASE. (MEAS. N 33° E, 120.74')
Az 127°, 78.36'; CENTERLINE OF NW BOLT OF LIGHT POLE BASE. (MEAS. S 53° E, 78.40')
Az 299°, 47.96'; CENTERLINE OF NE BOLT OF LIGHT POLE BASE. (MEAS. N 61° W, 47.98')
Az 337°, 106.65'; CENTERLINE OF NE BOLT OF LIGHT POLE BASE. (MEAS. N 23° W, 106.61')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

- G-10 (A): FOUND 1/2" IRON PIPE IN MONUMENT BOX IN FARMINGTON ROAD, 500' NORTH OF OBLITERATED CORNER G-10; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. 30086-26467.
N. 47° E. 85.93'; CENTERLINE OF SOUTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
S. 45° E. 93.50'; CENTERLINE OF NORTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
S. 39° W. 64.59'; CENTERLINE OF SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
N. 29° W. 83.69'; CENTERLINE OF SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
G-10 (B): FOUND MONUMENT (1/2" IRON PIPE) IN MONUMENT BOX IN FARMINGTON ROAD, 500' SOUTH OF OBLITERATED CORNER G-10; SET "WAYNE COUNTY REMONUMENTATION" TAG AND CAP NO. 30086-26467.
N. 33° E. 120.74'; CENTERLINE OF NORTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
S. 53° E. 78.41'; CENTERLINE OF NORTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
N. 61° W. 47.98'; CENTERLINE OF SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
N. 23° W. 106.61'; CENTERLINE OF SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by

Robert J. Smalley

Date

Dec 3, 1993

ROBERT J. SMALLEY

Surveyor's Michigan License No. 26467

Handwritten initials: 2R, 11D, M