

\$ 4.00 REMONUMENTATION  
 \$ 10.00 DEED  
 23 DEC 96 11:13 A.M. RECEI A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER EDG  
 WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located in: CITY OF LIVONIA	Corner Code #
1. Public Land Survey	T <u>1S</u> R <u>9E</u>	<u>G-11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Compliance with ACT 345, P.A. 1990 *DBJ*  
 APPROVED ON: 12-16-1996  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on NOV 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1816) POST  
 ELM 6' S 79°W 6 LINKS (GONE)  
 B. ASH 10' S 64°E 20 LINKS (GONE)  
 1937 - SHOWN ON PLAT OF 'SUPERVISOR'S LIVONIA PLAT No. 2', LIBER 66, PG 1  
 1930'S BUREAU OF TAXATION - FOUND IRON SE 85.70' MONUMENT  
 NW 61.83' EDISON POLE (GONE) SW 78.27' EDISON POLE (GONE)  
 NE 46.47' BASE OF SIGN POST (GONE) SE 51.04' TELE POLE (GONE)  
 (CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE IN MONUMENT BOX IN ASPHALT SURFACE AT THE INTERSECTION OF PLYMOUTH ROAD AND FARMINGTON ROAD. CHECKED CORNER WITNESS DISTANCES SHOWN IN R.C. 1079 AND DISTANCES TO F-11 AND G-12 AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:  
 FOUND 1" IRON IN MONUMENT BOX  
 N 56° E 71.82 P.K. NAIL IN S. FACE OF UTILITY POLE (MEAS 72.49)  
 N 18° W 74.57 'X' IN N.E. BOLT LIGHT POLE BASE (MEAS 74.37)  
 S 33° E 74.52 P.K. NAIL IN S.W. FACE UTILITY POLE (MEAS 74.37)  
 S 47° W 80.50 P.K. NAIL IN N.W. FACE UTILITY POLE (MEAS 79.97)  
 G-11 TO H-11 N 89°14'40" W 2650.35 RECORD 2650.16 MEASURED  
 G-11 TO G-12 S 00°01'00" W 2636.59 RECORD 2636.85 MEASURED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1" IRON PIPE IN A MONUMENT BOX AT THE INTERSECTION OF PLYMOUTH ROAD AND FARMINGTON ROAD. SET 'WAYNE COUNTY REMONUMENTATION' TAG AND SURVEY CAP No. 24618 IN THE IRON.  
 N 31° E 78.88 TOP NUT OF HYDRANT  
 N 46° E 72.49 SET NAIL AND 'WCR WITNESS' TAG IN S.E. SIDE OF UTILITY POLE  
 S 44° E 74.37 SET NAIL AND 'WCR WITNESS' TAG IN S.W. SIDE OF UTILITY POLE  
 S 22° E 99.83 TOP NUT OF HYDRANT  
 S 40° W 79.97 SET NAIL AND 'WCR WITNESS' TAG IN N.W. SIDE OF UTILITY POLE  
 N 44° W 81.40 TOP CENTER OF WAYNE COUNTY PRECISE BENCHMARK COVER  
 N 31° W 74.37 N.E. BOLT OF LIGHT POLE

THE SELECTED LOCATION AS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY THE PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer  
 Surveyor's Michigan License No. 24618

Date 11-29-1996 *DBJ*

## SECTION A (CONT)

- 1940 - SHOWN ON PLAT OF 'WALTER DANN SUBDIVISION', LIBER 67, PG 79
- 1974 - CERTIFICATE OF SURVEY #859, RECORDED IN LIBER 18738, PG 382  
DRAWING SHOWS S.W. CORNER OF SECTION 27  
AS A MONUMENT BOX
- 1976 - CERTIFICATE OF SURVEY #1188, RECORDED IN LIBER 19297, PG 375  
DRAWING SHOWS S.W. CORNER OF SECTION 27
- 1976 - CERTIFICATE OF SURVEY #1184, RECORDED IN LIBER 19297, PG 367  
DRAWING SHOWS S.W. CORNER OF SECTION 27
- 1977 - MORTGAGE REPORT CS #1334, RECORDED IN LIBER 19827, PG 959  
DRAWING SHOWS S.W. CORNER OF SECTION 27
- 1979 - CERTIFICATE OF SURVEY #1577, RECORDED IN LIBER 20520, PG 355  
N 50° W 78.8 BOLT AT N.E. CORNER OF LIGHT POLE (GONE)  
S 45° E 74.3 NAIL & TAG IN EDISON POLE (MEAS 74.37)  
S 45° W 80.15 P.K. NAIL IN EDISON POLE (MEAS 79.97)
- 1979 - CERTIFICATE OF SURVEY #1578, RECORDED IN LIBER 20520, PG 356  
N 50° W 78.8 BOLT AT N.E. CORNER OF LIGHT POLE (GONE)  
S 45° E 74.3 NAIL & TAG IN EDISON POLE (MEAS 74.37)  
S 45° W 80.15 P.K. NAIL IN EDISON POLE (MEAS 79.97)
- 1979 - CERTIFICATE OF SURVEY #1579, RECORDED IN LIBER 20520, PG 357  
N 50° W 78.8 BOLT AT N.E. CORNER OF LIGHT POLE (GONE)  
S 45° E 74.3 NAIL & TAG IN EDISON POLE (MEAS 74.37)  
S 45° W 80.15 P.K. NAIL IN EDISON POLE (MEAS 79.97)
- 1979 - CERTIFICATE OF SURVEY #1580, RECORDED IN LIBER 20520, PG 358  
N 50° W 78.8 BOLT AT N.E. CORNER OF LIGHT POLE (GONE)  
S 45° E 74.3 NAIL & TAG IN EDISON POLE (MEAS 74.37)  
S 45° W 80.15 P.K. NAIL IN EDISON POLE (MEAS 79.97)
- RECORDATION CERTIFICATE 1079, RECORDED IN LIBER 26670, PG 772 (1993)  
FOUND 1' IRON IN MONUMENT BOX  
N 56° E 71.82 P.K. NAIL IN S. FACE OF UTILITY POLE (MEAS 72.49)  
N 18° W 74.57 'X' IN N.E. BOLT LIGHT POLE BASE (MEAS 74.37)  
S 33° E 74.52 P.K. NAIL IN S.W. FACE UTILITY POLE (MEAS 74.37)  
S 47° W 80.50 P.K. NAIL IN N.W. FACE UTILITY POLE (MEAS 79.97)

FILE DO NOT MAIL