

\$ 4.00 REMONUMENTATION
 \$ 10.00 DEED
 23 DEC 96 11:13 A.M. RECEI A
 RECORDED
 WEST E. YOUNGBLOOD, REGISTER EDS
 WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located In: CITY OF LIVONIA	Corner Code # H-11
1. Public Land Survey	T 1S R 9E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990 *DBJ*
 APPROVED ON: 12-16-1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on NOV 13, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

- GL.D. (1816) POST AT AVERAGE DIST OF 40.10 CHAINS
 MAPLE 12' N 38°E 22 LINKS (GONE)
 POPLAR 6' N 37°W 18 LINKS (GONE)
- 1930'S BUREAU OF TAXATION - FOUND IRON
 NW 45.70' EDISON POLE SW 70.25' STONE POST
 NE 48.04' TELE GUY POLE SE 70.20' STONE POST (MEAS 69.46)
- 1950 - SHOWN ON PLAT OF 'ROSEDALE GARDENS No. 8' LIBER 71, PG 75
 (CONTINUED ON BACK)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MONUMENT BOX SET IN ASPHALT AT THE INTERSECTION OF PLYMOUTH ROAD AND HUBBARD. CHECKED CORNER WITNESS DISTANCES SHOWN IN BUREAU OF TAXATION 1930'S DATA AND DISTANCES TO G-11 AND H-12 AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:

SE 70.20' STONE POST (MEAS 69.46 TO N.W. CORNER, AND 70.4 COMPUTED TO CENTER)

H-11 TO G-11 S 89°14'40" E 2650.35 RECORD 2650.16 MEASURED
 H-11 TO H-12 2636.70 COMPUTED FROM PLAT 2638.66 MEASURED
 H-12 IS MISSING AND WAS TEMPORARY RECREATED FROM ADJOINING PLATS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1/2" IRON IN MONUMENT BOX AT THE INTERSECTION OF PLYMOUTH ROAD AND HUBBARD ROAD. SET 'WAYNE COUNTY REMONUMENTATION' TAG AND SURVEY CAP No. 24618 IN IRON.

N 27° E 81.30 SET NAIL AND 'WCR WITNESS' TAG IN N.W. SIDE OF EDISON POLE
 N 50° E 94.73 S.W. CORNER OF BILL BROWN BUILDING
 S 37° E 64.40 SET NAIL AND 'WCR WITNESS' TAG IN N.E. SIDE OF UTILITY POLE
 S 27° E 69.46 N.W. CORNER OF STONE PILLAR
 S 35° W 72.54 INTERSECTION OF BACK OF CONC. SIDEWALKS
 N 41° W 69.26 TOP NUT OF HYDRANT

THE SELECTED LOCATION AS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY THE PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer
 Surveyor's Michigan License No. 24618

Date 11-23-1996

SECTION A (CONT)

RECORDATION CERTIFICATE 95, RECORDED IN LIBER 18128, PG 376
FOUND 1/2" IRON IN HANDHOLE
N 43° E 48.0 P.K. NAIL IN POWER POLE (GONE)
S 43° E 63.60 P.K. NAIL IN POWER POLE (MEAS 64.40)
N 39° W 60.80 P.K. NAIL IN POWER POLE (GONE)

FILE DU NOT MAIL