

**SURVEY & REMONUMENTATION**

**RC 1475**

**APR 25 1995**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing requirement of Act 74, Mich. P.A. 1970**

**COMMISSION**

\$ 13.00 MISCELLANEOUS RECORDING  
 89 APR 25 3:39 P.M. RECEIPT# 93A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

For corners in WAYNE COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 1 S R 9 E H - 13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**L127796PA703**

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 12-12-94  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on AUGUST 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"  
 WPA SURVEY (1930'S) "FOUND IRON, REPLACED WITH 4'0" CONCRETE MONUMENT"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND HUBBARD ROAD. CHECKED CORNER WITNESSES AND DISTANCE TO I-13 AGAINST DISTANCES MEASURED BY WPA SURVEY AS FOLLOWS:

N.E. 75.05'; "+" IN EDGE MICH. BELL M. H. RING (MEAS. N 60° E, 75.11')  
 EAST 85.18 MONUMENT - N. 1/4 COR. SEC. 3, NANKIN (MEAS. EAST, 85.45')

H-13 TO I-13 N 89°43'30" W. 2687.56 (MEAS. 2687.92')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2 BAR) IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND HUBBARD ROAD (CONCRETE PAVEMENT); SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER BAR IN MONUMENT.

EAST 85.45'; FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT CORNER H-1 (WESTLAND)  
 N. 34° E. 61.99'; SET NAIL AND "WCR WITNESS" TAG IN SE FACE OF UTILITY POLE.  
 N. 65° E. 75.11'; CLOSEST RIM OF M.B.T. MANHOLE.  
 S. 35° W. 46.66'; SET CUT CROSS IN NORTH CORNER OF CONCRETE TRAFFIC SIGNAL BASE.  
 N. 35° W. 74.03'; FOUND CONCRETE MONUMENT AT NW CORNER OF JOY RD. AND HUBBARD RD.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date 12-22-94  
 ROBERT J. SMALLEY  
 Surveyor's Michigan License No. 26467

