

SURVEY & REMONUMENTATION

RC 1476

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

WAYNE COUNTY

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>1 S</u> | R | <u>9 E</u> | <u>I-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA(1930'S): "MONUMENT"

\$ 13.00 MISCELLANEOUS RECORDING
 22 DEC 94 3:39 P.M. RECEIPT# 93A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND MERRIMAN ROAD. CHECKED CORNER DISTANCES TO I-12, H-13 AND I-1(WESTLAND) AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:

I-13 TO I-12	N. 00°19'50" W.	2628.81'	(MEAS. 2628.95')
I-13 TO H-13	N. 89°43'30" W.	2687.56'	(MEAS. 2687.92')
I-13 TO I-1 (WESTLAND)	EAST	49.20'	(MEAS. 49.20')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX (IN PAVEMENT) AT THE INTERSECTION OF JOY ROAD AND MERRIMAN ROAD); SET "WAYNE COUNTY REMONUMENTATION" TAG AND CAP No. "30086-26467" OVER BAR IN MONUMENT.

EAST	49.20';	FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT OR NEAR CORNER I-1 (WESTLAND).
S. 57° E.	95.60';	SET NAIL AND "WCR WITNESS" TAG IN SOUTHWEST FACE OF UTILITY POLE
S. 17° W.	70.76';	SET NAIL AND "WCR WITNESS" TAG IN WEST FACE OF UTILITY POLE
N. 28° W.	61.45';	SET NAIL AND "WCR WITNESS" TAG IN NORTHEAST FACE OF UTILITY POLE
N. 39° E.	91.78';	SET CUT CROSS IN SOUTHWEST BOLT OF STREET LIGHT BASE

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

L127796PA704

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-12-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RC 1476

