

FEB 25 1994

COMMISSION

RC 1229

LAND CORNER RECORDATION CERTIFICATE  
Filing requirement of Act 74, Mich. P.A. 1970

L127004PA585

For corners in WAYNE COUNTY Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 1 S R 9 E K-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12/3/93 WCS  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
- WPA (1930's): "IRON NW-13"
- LCRC (1972): "FOUND MONUMENT IN ROAD BOX" (RC-152; L. 18258, P. 152)
- LCRC (1977): "CONCRETE MONUMNET IN BOX" (RC-544; L. 19935, P. 375)
- LCRC (1992): "FOUND CONCRETE MONUMENT IN MONUMENT BOX" (RC-1043; L. 25755, P. 660)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" IRON BAR) IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN RC-1043 AS FOLLOWS:

- Az. 311°, 77.91'; CHISELED "X" IN S.E. BOLT OF LIGHT POLE BASE. (MEAS. N 57° W, 77.89')
- Az. 60°, 82.07'; CHISELED "X" IN S.W. BOLT OF LIGHT POLE BASE. (MEAS. N 29° E, 70.28')
- Az. 131°, 77.28'; CHISELED "X" IN N.W. BOLT OF LIGHT POLE BASE. (MEAS. S 56° E, 77.29')
- Az. 218°, 77.91'; CHISELED "X" IN N.E. BOLT OF LIGHT POLE BASE. (MEAS. S 31° W, 74.68')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" IRON BAR) IN MONUMENT BOX AT INTERSECTION OF SIX MILE ROAD AND MIDDLEBELT ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER IRON BAR IN MONUMENT.

- N. 52° W. 84.19'; FOUND CHISELED "X" IN SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
- N. 40° E. 73.53'; FOUND CHISELED "X" IN SOUTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
- S. 58° E. 77.64'; FOUND CHISELED "X" IN NORTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
- S. 40° W. 79.44'; FOUND CHISELED "X" IN NORTHEAST BOLT OF CONCRETE LIGHT POLE BASE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993  
Surveyor's Michigan License No. 26467

NOV 30 1993  
 RC-1043  
 215R  
 M