

CLERK OF COURTS
 COUNTY OF WAYNE
 FEB 29 1994

RC 1231

LI27004PA587

LAND CORNER RECORDATION CERTIFICATE
 Filing requirement of Act 74, Mich. P.A. 1970

For corners in
WAYNE COUNTY
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>1 S</u>	R <u>9 E</u>	<u>K-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12/3/93 YCAL
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA (1930's): "IRON NW-36"

28
 11D
 M

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX AT INTERSECTION OF PLYMOUTH ROAD AND MIDDLEBELT ROAD; CHECKED DISTANCE TO CORNER J-11, WAYNE COUNTY SECTION MAPS SHOW AVERAGE DISTANCE TO BE 2623.00', MEASUREMENT ON 11/23/93 EQUALS 2623.57'; CHECKED DISTANCE TO K-12, SECTION MAPS SHOW AVERAGE DISTANCE TO BE 2638.06', MEASUREMENT EQUALS 2638.34'. ACCEPTED LOCATION AS FOUND.


C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX AT INTERSECTION OF PLYMOUTH ROAD AND MIDDLEBELT ROAD; SET 1/2" PIPE AND "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" INSIDE PIPE IN MONUMENT.

- N. 49° W. 81.78'; SET NAIL AND "WCR WITNESS" TAG IN NORTHEAST SIDE OF UTILITY POLE.
- N. 46° E. 71.13'; SET NAIL AND "WCR WITNESS" TAG IN SOUTHWEST SIDE OF UTILITY POLE.
- S. 42° E. 79.86'; SET NAIL AND "WCR WITNESS" TAG IN NORTHEAST SIDE OF UTILITY POLE.
- S. 51° W. 101.41'; SET NAIL AND "WCR WITNESS" TAG IN NORTHWEST SIDE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467



DEC-3 PM 12:19
 1993