

\$ 4.00 REMONUMENTATION
\$ 7.00 DEED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED DEC 96 11:13 A.M.
RECORDED
FOREST E. YOUNGBLOOD, REGISTER
WAYNE COUNTY, MI

For corners in

<u>WAYNE</u> (County)	Located In: <u>CITY OF LIVONIA</u>	Corner Code # <u>K-12</u>
1. Public Land Survey	T <u>1S</u> R <u>9E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-16-1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____


I, PAUL V. SCHWIMMER, in a field survey on NOV 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.D. (1816) POST
- CYPRUS 9° N 05° W 6 LINKS (GONE)
- CYPRUS 6° S 78° W 20 LINKS (GONE)
- 1930'S BUREAU OF TAXATION - FOUND IRON
- NW 66.37' EDISON POLE (GONE) SW 59.75' 14' ELM (GONE)
- NE 51.30' CONC. SIGN (GONE) SE 35.23' TELE POLE (GONE)
- 1954 - SHOWN ON PLAT OF 'BEL-AIRE GARDENS' LIBER 75, PG 48
- 1954 - SHOWN ON PLAT OF 'PEARL WILSON SUB'N' LIBER 76, PG 10



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON IN CONC. AT THE BOTTOM OF A MONUMENT BOX SET IN AN ASPHALT ROAD SURFACE. I ALSO FOUND A NUMBER OF WITNESS TAGS IN UTILITY POLES THAT DO NOT HAVE RECORDATION CERTIFICATES. CHECKED THE DISTANCES TO I-12, K-13, AND L-12 AGAINST DISTANCES MEASURED BY WPA SURVEYS OF THE 1930'S.

K-12 TO I-12 WESTERLY	5308.90 COMPUTED	5302.07 MEASURED
K-12 TO K-13 SOUTHERLY	2634.52 RECORDED	2634.07 MEASURED
K-12 TO L-12 N 89° 51' 00" (UNKNOWN)	2641.15 RECORDED	2641.71 MEASURED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RAISED 1" IRON FOUND IN CONCRETE AT THE BOTTOM OF A MONUMENT BOX WITH A 4" LENGTH OF 5/8" IRON. I THEN SET A 'WAYNE COUNTY REMONUMENTATION' TAG AND SURVEY CAP No. 24618. THE 5/8" IRON WAS SECURELY DRIVEN INTO THE 1" IRON TO REFUSAL.

- N 43° E 75.30 SET NAIL AND 'WCR WITNESS' TAG IN N.W. SIDE OF WOOD SIGNAL GUY POLE
- S 70° E 105.51 TOP NUT OF HYDRANT
- S 50° E 69.59 SET NAIL AND 'WCR WITNESS' TAG IN N.E. SIDE OF UTILITY POLE
- S 58° W 61.15 SET NAIL AND 'WCR WITNESS' TAG IN N.W. SIDE OF UTILITY POLE
- S 63° W 80.10 TOP NUT OF HYDRANT
- N 57° W 62.52 SET NAIL AND 'WCR WITNESS' TAG IN S.W. SIDE OF UTILITY POLE
- N 35° W 60.02 N.E. BOLT ON LIGHT POLE SIDE OF UTILITY POLE

THE SELECTED LOCATION AS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY THE PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

4R
7D
D.D.

Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date 11-27-1996