

FEB 29 1994

L127004 PA588

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
WAYNE COUNTY
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 1 S R 9 E L-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12/3/93 YCO
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
WPA (1930's): "CROSS N-24"
LCRC (1981): "FOUND IRON IN BOX" (RC-752; L. 21083, P. 67)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN RC-752 AS FOLLOWS:

N.W., 63.84'; CENTER OF N.E. BOLT OF METAL LIGHT POLE. (MEAS. N 43° W, 63.85')
N.E., 74.62'; TOP NUT ON FIRE HYDRANT. (MEAS N 29° E, 75.04')
S.E., 63.58'; CENTER OF S.W. BOLT OF METAL LIGHT POLE. (MEAS. S 43° E, 63.51')
S.W., 65.54'; CHISELED CROSS ON KEYFLAG OF SIDEWALK. (MEAS. S 35° W, 65.59')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" PIPE IN MONUMENT BOX AT INTERSECTION OF FIVE MILE ROAD AND HARRISON ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" INSIDE PIPE.

N. 43° W. 63.85'; FOUND CENTER OF NORTHEAST BOLT OF CONCRETE LIGHT POLE BASE.
N. 29° E. 75.04'; FOUND CENTER OF TOP NUT ON FIRE HYDRANT.
S. 43° E. 63.51'; FOUND CENTER OF SOUTHWEST BOLT OF CONCRETE LIGHT POLE BASE.
S. 35° W. 65.59'; FOUND CHISELED "X" IN KEYFLAG OF SIDEWALK.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
ROBERT J. SMALLEY

Surveyor's Michigan License No. 26467

26
110
M

RECORDED
INDEXED
DEC 3 1993
RECORDS
DIVISION
MICHIGAN

