

DEC 28 1998

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 02 1999

For corners in

WAYNE
(County)

Located In:
CITY OF LIVONIA

Corner Code #

1. Public Land Survey

T 1S R 9E L-11

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

SECTION

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, PAUL V. SCHWIMMER, in a field survey on NOV 19, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GOVERNMENT LAND OFFICE (1816) SET 1/4 POST 1930'S WAYNE COUNTY BUREAU OF TAXATION WITNESSES;
BEECH 12" N 52°W .13 CHAINS (1) (GONE) IRON PIPE
SUGAR 4" N 80°E .08 CHAINS (2) (GONE) NORTH 32.32' ED. POLE (3) (GONE)
S.W. 71.32' TEL. POLE (4) (GONE)
S.W. 58.90' TEL. POLE (5) (GONE)

L-11 IS SHOWN ON THE PLAT OF "THOMAS ELLIOT SUBDIVISION" AS RECORDED IN LIBER 72, PAGE 19, W.C.R. (1950)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A CONCRETE NAIL AT THE POSITION OF L-11. THIS NAIL WAS APPROXIMATELY .7 WEST OF WHAT APPEARS TO BE A HAND HOLE IN THE ASPHALT ROAD. I ALSO FOUND AN IRON PIPE IN A MONUMENT POSITION AS WELL AS CORRESPONDING MEASUREMENTS TO ADJACENT CORNERS. MY MEASUREMENTS INDICATE THAT THE NAIL WAS SET USING PRORATED MEASUREMENTS OF THE 1930'S REMONUMENTATION EFFORT OF THE SOUTH LINE OF SECTION 25.

- * L-11 TO L-12: 2845.05 COMPUTED VERSUS 2845.55 MEASURED.
- * L-11 TO M-11: 2652.09 RECORDED VERSUS 2652.27 MEASURED.
- * L-11 TO K-11: 2650.06 RECORDED VERSUS 2650.19 MEASURED.
- * THE ANGLE OF K-11 - L-11 - M-11 IS 179°52'40" RECORDED VERSUS 179°53'31" MEASURED.

\$4.00 REMONUMENTATION
\$7.00 DEED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONCRETE NAIL SET IN C/L OF PLYMOUTH ROAD (ASPHALT) AT THE CENTERLINE INTERSECTION OF HARRISON ROAD. RESET WITH CONCRETE MONUMENT AND MONUMENT BOX, SET REMON. TAG ON MONUMENT.
N 54°E 61.21' S.W. BOLT OF LIGHT POLE BASE.
S 37°E 53.39' N.W. BOLT ON TRAFFIC CROSSING SIGNAL BASE.
S 34°E 78.10' N.W. CORNER OF BRICK BUILDING
S 54°W 61.93' N.E. BOLT OF LIGHT POLE BASE.
N 35°W 62.09' POWER POLE WITH NAIL & REMON. TAG IN S.W. SIDE

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Receipt #101787

Signed by Paul V. Schwimmer

Date 12-20-98

Surveyor's Michigan License No. 24618

R. LCR 7 4R 1P6 U. DPJ

Liber-30034

Page-445.0

12/28/1998 09:12AM