

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in WAYNE COUNTY Located In: LIVONIA Corner Code # \_\_\_\_\_  
(County)

LIBER **28465** PAGE **791**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-13-95 *DBJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey T 1 S R 9 E M - 1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"  
WPA SURVEY (1930'S) "IRON"

\$ 4.00 REMONUMENTATION  
\$ 7.00 DEED  
15 DEC 95 11:22 A.M. RECEI  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER  
WAYNE COUNTY, MI

95268807

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" BAR IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND EIGHT MILE ROAD. CHECKED DISTANCE TO M-2 AGAINST DISTANCES MEASURED BY WPA SURVEY AND DISTANCE FROM SECTION LINE TO FOUND IRON BAR AT NE CORNER OF ASSESSOR'S PLAT LIVONIA SUB. AS FOLLOWS:

M-1 to M-2 - S 0°28'40" W, 2643.28' (MEAS. 2643.29')  
E. LINE SECTION 1 to NE CORNER SUB. R. 60.00' (MEAS. 59.95')

NOTE: CORNER IS COMMON WITH CORNER A-1 OF REDFORD TOWNSHIP, T. 1 S., R. 10 E.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1" BAR IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND EIGHT MILE ROAD (CONCRETE PAVEMENT); STAMPED TOP OF 1" BAR WITH LETTERS "M-1".

- N. 22° W. 98.67'; SET PK NAIL AND "WCR WITNESS" TAG IN NE FACE OF UTILITY POLE.
- N. 15° E. 122.94'; SET PK NAIL AND "WCR WITNESS" TAG IN SE FACE OF UTILITY POLE.
- S. 24° E. 116.06'; SET PK NAIL AND "WCR WITNESS" TAG IN NE FACE OF UTILITY POLE.
- S. 21° W. 109.18'; SET PK NAIL AND "WCR WITNESS" TAG IN SE FACE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date Dec 13, 1995  
ROBERT J. SMALLEY

Surveyor's Michigan License No. 26467

