

SURVEY & REMONUMENTATION

RC 1479

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE

Filing requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING
 22 DEC 94 3:40 P.M. RECEIPT# 93A
 RECORDED
 E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

L27796PA707

COMMISSION

For corners in

WAYNE COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>M - 5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-12-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
- WPA SURVEY (1930'S) "IRON"
- LCRC (1977): "CONCRETE MONUMENT IN BOX" (RC 546; L. 19935, P. 379)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND SIX MILE ROAD. CHECKED CORNER WITNESSES RECORDED IN RC 546 AND DISTANCE TO M-6 AGAINST DISTANCES MEASURED BY WPA SURVEY AS FOLLOWS:

- NORTH 40.64'; CONCRETE MON. IN BOX AT N.W. CORNER OF SEC.18, T. 1 S., R. 10 E. (MEAS. NORTH, 40.72')
- S.E. 51.62'; P.K. NAIL IN SW. SIDE OF DETROIT EDISON POLE WITH LIGHT (MEAS. S 80° E, 51.54')
- S.W. 71.82'; CENTER OF N.E. BOLT OF SHELL OIL SIGN POST BASE (MEAS. S 61° W, 71.82')
- M-5 to M-6 - S 0°05'17" W, 2643.72' (MEAS. 2643.69')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND SIX MILE ROAD (CONCRETE PAVEMENT); SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER IRON PIPE IN MONUMENT.

- NORTH 40.72'; FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT CORNER A-5 (REDFORD)
- N. 29° E. 104.75'; SET NAIL AND "WCR WITNESS" TAG IN SE FACE OF UTILITY POLE. Z R
- S. 80° E. 51.54'; SET NAIL AND "WCR WITNESS" TAG IN SOUTH FACE OF UTILITY POLE. 11 D
- S. 61° W. 71.82'; CENTER LINE OF NE BOLT OF SHELL OIL COMPANY SIGN BASE. MISC
- N. 30° W. 104.03'; SET NAIL AND "WCR WITNESS" TAG IN SW FACE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

