

**SURVEY & REMONUMENTATION**

**RC 1480**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING  
 23 DEC 94 3:40 P.M. RECEIPT# 93A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI  
**LI 27796PA708**

For corners in  
**COMMISSION**  
**WAYNE COUNTY**  
 (County)

Located In:

Corner Code #

- |                                    |              |              |              |
|------------------------------------|--------------|--------------|--------------|
| 1. Public Land Survey              | T <u>1 S</u> | R <u>9 E</u> | <u>M - 6</u> |
|                                    | T _____      | R _____      | _____        |
|                                    | T _____      | R _____      | _____        |
|                                    | T _____      | R _____      | _____        |
| 2. Property Controlling in Section | S _____      | R _____      | _____        |
|                                    | S _____      | R _____      | _____        |
| 3. Miscellaneous Property in Sec.  | S _____      | R _____      | _____        |
|                                    | S _____      | R _____      | _____        |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 12-22-94  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, **ROBERT J. SMALLEY**, in a field survey on **NOVEMBER 14, 1994**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"  
 WPA (1930'S): "FOUND 1" SQUARE OAK STAKE 23.38' SOUTH OF W 1/4 CORNER SEC. 18 REDFORD. REPLACED WITH 4'-0" CONCRETE MONUMENT - IN CLAY - TOP OF MON 6" ABOVE GROUND."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX; CHECKED DISTANCES TO M-5, M-7 AND A-6 (REDFORD) AGAINST DISTANCES MEASURED BY WPA SURVEY AS FOLLOWS:

M-6 TO M-5 - N 0°05'20" E,	2643.72'	(MEAS. 2643.69')
M-6 TO M-7 - S 0°07'20" W,	2643.00'	(MEAS. 2642.88')
M-6 TO A-6 (REDFORD)	12.38'	(MEAS. 12.39')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX IN THE CENTER LINE OF INKSTER ROAD (ASPHALT PAVEMENT). SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER BAR IN MONUMENT.

NORTH	12.39'	FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT CORNER A-6 OF REDFORD TOWNSHIP.
EAST	25.74'	BACK OF CONCRETE CURB (NEWLY CONSTRUCTED IN THE SUMMER OF 1994)
SOUTH	94.60'	NORTH EDGE OF BRIDGE DECK AT CENTER CONSTRUCTION JOINT.
S. 56° W.	39.03'	SET PK NAIL IN TOP OF POST OF GUARD RAIL, WEST SIDE OF INKSTER ROAD.
N. 64° W.	36.02'	SET PK NAIL IN TOP OF POST OF GUARD RAIL, WEST SIDE OF INKSTER ROAD.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date 12-22-94  
 ROBERT J. SMALLEY  
 Surveyor's Michigan License No. 26467

