

SURVEY & REMONUMENTATION

RC 1481

L127796PA709

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

MISCELLANEOUS RECORDING
 22 DEC 94 3:40 P.M. RECEIPT# 93A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

For corners in WAYNE COUNTY (County) Located In: Corner Code #

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>M-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-94
 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA SURVEY (1930'S) "IRON"
 LCRC (1990): "FOUND IRON PIPE IN MONUMENT BOX" (RC 1018; L. 25426, P. 950)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND FIVE MILE ROAD. CHECKED WITNESSES RECORDED IN RC 1018 AND DISTANCES TO M-6 AND L-7 AGAINST DISTANCES MEASURED BY WPA SURVEY AS FOLLOWS:

N. 22° W. 71.94'; P.K. NAIL W/ TAG - NE FACE OF UTILITY POLE (MEAS. N 45° W, 71.08')
 N. 32° E. 67.92'; P.K. NAIL W/ TAG - SE FACE OF UTILITY POLE (MEAS. N 40° E, 67.98')
 S. 45° E. 66.72'; P.K. NAIL W/ TAG - SW FACE UTILITY POLE (MEAS. S 47° E, 66.62')
 S. 29° W. 114.96'; P.K. NAIL W/ TAG - WEST FACE UTILITY POLE. (MEAS. S 23° W, 114.99')

M-7 to M-6 - N 0°07'20" W, 2643.00' (MEAS. 2642.88')
 M-7 to L-7 - S 89°59'40" W, 2641.05' (MEAS. 2640.93')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND FIVE MILE ROAD (CONC. PAVEMENT); SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP NO. "30086-26467" OVER IRON PIPE IN MONUMENT.

N. 45° W. 71.08'; SET NAIL AND "WCR WITNESS" TAG IN NE FACE OF UTILITY POLE.
 N. 40° E. 67.98'; SET NAIL AND "WCR WITNESS" TAG IN SE FACE OF UTILITY POLE.
 S. 47° E. 66.62'; SET NAIL AND "WCR WITNESS" TAG IN SW FACE OF UTILITY POLE.
 S. 23° W. 114.99'; SET NAIL AND "WCR WITNESS" TAG IN WEST FACE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467



*Z R
 11 D
 MISC.*