

**SURVEY & REMONUMENTATION**

**RC 1482**

**LI27796PA710**

**APR 25 1995**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing requirement of Act 74, Mich. P.A. 1970**

MISCELLANEOUS RECORDING  
22 DEC 94 3:41 P.M. RECEIPT# 93A  
RECORDED

**COMMISSION**

FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

Compliance with  
ACT 345, P.A. 1990.

APPROVED ON: 12-12-94  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

For corners in  
WAYNE COUNTY  
(County) Located In: Corner Code #

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>M - 08</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"

WPA(1930'S): "FOUND STAKE - 1-1/2" SQUARE - TOP BROKEN OFF 4"-5" BELOW GROUND REPLACED WITH 4'-0" CONCRETE MONUMENT - TOP OF MON 6" BELOW SURFACE."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT ( WITH 1/2" PIPE ) IN MONUMENT BOX IN THE CENTER OF INKSTER ROAD. CHECKED CORNER WITNESSES TO M-8 (AND A-8 OF REDFORD) AGAINST WPA SURVEY DISTANCES AND AGAINST FOUND POINTS IN SUPERVISOR'S REDFORD PLAT NO. 3 (L. 69, P. 54) AS FOLLOWS:

M-8 to A-8 -	44.2'	(MEAS. 44.76')
M-8 to SW CORNER OF LOT 129 OF SUPERVISOR'S REDFORD PLAT No. 3 -	62.94'	(MEAS. 62.64')
PERPENDICULAR DISTANCE FROM M-8 TO WEST LINE OF PLAT	60.00'	(MEAS. 60.00')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX IN THE CENTER LINE OF INKSTER ROAD (ASPHALT PAVEMENT) SOUTH OF LYNDON ROAD TO THE EAST AND NORTH OF LYNDON ROAD TO THE WEST; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP No. "30086-26467" OVER PIPE IN MONUMENT.

NORTH	44.76';	FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX AT CORNER A-8 (REDFORD).
N. 54° E.	74.75';	FOUND CONCRETE MONUMENT AT ANGLE POINT IN WEST LINE OF LOT 129 OF SUPERVISOR'S REDFORD PLAT No. 3.
S. 73° E.	62.64';	FOUND CONCRETE MONUMENT AT THE SW CORNER OF SAID LOT 129.
WEST	59.95';	SET NAIL WITH "WCR WITNESS" TAG IN NORTH SIDE OF UTILITY POLE.
N. 68° W.	70.18';	SET NAIL WITH "WCR WITNESS" TAG IN NORTH SIDE OF 12" PINE TREE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date 12-22-94  
ROBERT J. SMALLEY

Surveyor's Michigan License No. 26467

