

**SURVEY &
REMONUMENTATION**

RC 1483

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE

Filing requirement of Act 74, Mich. P.A. 1970

L127796PA711

COMMISSION

For corners in
WAYNE COUNTY
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 1 S R 9 E M - 09
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-12-94

**WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE**

Register of Deeds Stamp & File Number

I, **ROBERT J. SMALLEY**, in a field survey on **DECEMBER 16, 1994**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
WPA(1930'S): "FOUND 3/4" IRON - REPLACED WITH 4'-0" CONCRETE MONUMENT.
(MONUMENT DESTROYED BY FREEWAY CONSTRUCTION)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DRILLED HOLE AND SET "P.K." NAIL WITH "WCR WITNESS" TAG IN CONCRETE BRIDGE DECK OF THE MERRIMAN ROAD BRIDGE OVER THE I-96 FREEWAY (SCHOOLCRAFT ROAD). CHECKED DISTANCE MEASURED BY MDOT AND THE WPA SURVEY OF THE 1930'S TO M-8 AND M-10 AND DISTANCE TO MDOT WITNESS MONUMENT.

M-9 to M-8 - WPA 2637.20' MDOT 2637.50' (MEAS. 2637.33')
M-9 TO M-10 - WPA 2537.17' MDOT 2737.58' (MEAS. 2637.36')
M-9 TO SOUTH WITNESS MONUMENT - MDOT 300.00' (MEAS. 299.93')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

DRILLED HOLE AND SET "P.K." NAIL WITH "WCR WITNESS" TAG IN CONCRETE BRIDGE DECK OF MERRIMAN ROAD BRIDGE OVER THE I-96 FREEWAY (SCHOOLCRAFT ROAD).

N. 38° E. 65.13'; NORTHWEST CORNER OF CONCRETE BRIDGE RAILING
S. 58° E. 47.21'; SOUTHEAST CORNER OF CONCRETE BRIDGE RAILING
S. 58° W. 47.21'; SOUTHWEST CORNER OF CONCRETE BRIDGE RAILING
N. 51° W. 51.62'; CENTER OF SOUTHEAST BOLT OF LIGHT BASE ON CONCRETE BRIDGE RAIL.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

13.00 MISCELLANEOUS RECORDING
22 DEC 94 3:41 P.M. RECEIPT# 93A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

Signed by Robert J. Smalley Date 12-22-94
ROBERT J. SMALLEY
Surveyor's Michigan License No. 26467

