

SURVEY & REMONUMENTATION

RC 1485

\$ 13.00 MISCELLANEOUS RECORDING

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing requirement of Act 74, Mich. P.A. 1970

MISCELLANEOUS RECORDING
 23 DEC 94 3:41 P.M. RECEIPT# 93A
 RECORDED

COMMISSION

FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
L27796PA713

For corners in WAYNE COUNTY Located In: Corner Code #
 (County)

- 1. Public Land Survey T 1 S R 9 E M - 12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-22-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1816): "POST"
- WPA(1930'S): "MONUMENT"
- LCRC (1972) "FOUND CONCRETE MONUMENT IN MONUMENT BOX" (RC 746, L. 21061, P. 669)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND WEST CHICAGO ROAD. CHECKED CORNER WITNESSES DISTANCES SHOWN IN RC 746 (L. 21061, P. 664) AND DISTANCE FROM M-12 TO M-13 AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:

NORTH 67.96'(RC746) 68.00'(WPA) "FD MON. IN MON. BOX" (MEAS. NORTH 67.94')
 N. 30° E. 111.50' "PK NAIL IN WEST SIDE OF POWER POLE" (MEAS. N. 31° E. 111.53')
 S. 70° W. 51.77' "PK NAIL IN NORTH SIDE OF POWER POLE" (MEAS. S. 69° W. 51.32')

M-12 TO M-13 S. 00°13'40" E. 2648.54' (MEAS. 2648.77')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX AT THE INTERSECTION OF INKSTER ROAD AND WEST CHICAGO ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP No. "30086-26467" IN PIPE OF MONUMENT.

- NORTH 67.94' FOUND CONCRETE MONUMENT (WITH 1" PIPE) IN MONUMENT BOX AT OR NEAR CORNER A-12 (REDFORD).
- N. 26° E. 111.53'; SET NAIL AND "WCR WITNESS" TAG IN NORTHWEST FACE OF UTILITY POLE 2R
- S. 89° E. 44.14'; SET NAIL AND "WCR WITNESS" TAG IN SOUTH FACE OF UTILITY POLE 11 D
- S. 63° W. 51.32'; SET NAIL AND "WCR WITNESS" TAG IN NORTHWEST FACE OF UTILITY POLE
- N. 31° W. 90.66'; SET CUT CROSS IN SOUTHEAST BOLT OF CONCRETE LIGHT POLE BASE MISC

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

