

SURVEY & REMONUMENTATION

RC 1486

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing requirement of Act 74, Mich. P.A. 1970

L127796PA714

For corners in WAYNE COUNTY (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>1 S</u>	R <u>9 E</u>	<u>M - 13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____ T _____	R _____	_____
	S _____ T _____	R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	R _____	_____
	S _____ T _____	R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12/12/94
 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on SEPTEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA(1930'S): "IRON"
 LCRC (1972) "FOUND IRON IN MONUMENT BOX" (RC 746, L. 21061, P. 669)

\$ 13.00 MISCELLANEOUS RECORDING
 22 DEC 94 3:41 P.M. RECEIPT# 93A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND INKSTER ROAD. CHECKED CORNER WITNESSES DISTANCES SHOWN IN RC 746 (L. 21061, P. 664) AND DISTANCES TO L-13 AND M-12 AGAINST DISTANCES MEASURED BY WPA SURVEY OF 1930'S AS FOLLOWS:

N. 55° E.	68.65'	"PK NAIL IN SE SIDE OF POWER POLE"	(MEAS.	N. 55° E.	68.79')
S. 50° E.	62.67'	"PK NAIL IN SW SIDE OF POWER POLE"	(MEAS.	S. 50° E.	62.68')
SOUTHWEST	86.28'	"CORNER OF DRUG STORE"(WPA)	(MEAS.	S. 58° E.	86.19')

M-13 TO M-12	N. 00°13'40" W.	2648.54'	(MEAS. 2648.77')
M-13 TO L-13	N. 89°57'40" W.	2653.54'	(MEAS. 2653.86')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" BAR) IN MONUMENT BOX AT THE INTERSECTION OF JOY ROAD AND INKSTER ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP No. "30086-26467" OVER 1/2" BAR IN MONUMENT.

N. 55° E.	68.79';	SET NAIL AND "WCR WITNESS" TAG IN NORTHWEST FACE OF UTILITY POLE
S. 50° E.	62.68';	SET NAIL AND "WCR WITNESS" TAG IN SOUTHWEST FACE OF UTILITY POLE
S. 50° W.	86.19';	NORTHEAST CORNER OF BUILDING NO. 27405 JOY ROAD
N. 41° W.	71.80';	SET NAIL AND "WCR WITNESS" TAG IN SOUTHWEST FACE OF UTILITY POLE

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date 12-22-94
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

