

SURVEY & REMONUMENTATION

APR 25 1995

RC 1555

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 8:19 A.M. RECEIPT# 12R
RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

L127800PA046

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-8-94
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1555

For corners in Wayne (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>1</u> S <u>R</u> 10 E	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		18		19		20		21	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11		●											
12		31		32		33		34		35		36	
13													

I, William L. Roskelly in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11) SOUTH CORNER SECTION 30, T.1 S., R.10 E.
G.L.O. (1830's) Joseph Fletcher set corner post witnesses: Beech 12 S. 65 W. 31, Do 9 N. 22 W. 21.
W.P.A. (1930's) found iron witnesses: N.W. 55.34 Telephone pole (gone) S.W. 74.85 monument (not found), S.E. 53.25 Telephone pole (gone). S.E. 72.92 monument (not found).
No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11) SOUTH CORNER SECTION 30, T.1 S., R.10 E.
Found a square iron pipe in a mon. box at the intersection of Plymouth and Hemmingway Roads. Verified corner location by comparing W.P.A. data with field measurements:
B-11 to A-11 Record = 2429.08 Measured = 2429.51
B-11 to B-12 Record = none Measured = 2677.00
B-11 to C-11 Record = 2595.66 Measured = 2596.12
Angle line B-11 & A-11 to line B-11 & B-12 Record = 88° 17' 02" Measured = 88° 17' 02"
Angle line B-11 & B-12 to line B-11 & C-11 Record = 91° 29' 40" Measured = 91° 30' 11"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11) SOUTH CORNER SECTION 30, T.1 S., R.10 E.
Found a square iron pipe in a mon. box at the intersection of Plymouth and Hemmingway Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
WITNESSES:
Set nail & W.C.R. tag N.W. face P. pole N. 38° E. Dist. = 71.29
N.W. bolt of sign post conc. base S. 33° E. Dist. = 75.21
Set nail & W.C.R. tag S.E. face P. pole S. 40° W. Dist. = 54.75
Set nail & W.C.R. tag S.W. face P. pole N. 30° W. dist. = 56.11
Placed Wayne County Remonumentation brass marker and cap #10705

2R
11-D
MISC

Signed by William L. Roskelly Date 12/27/94
Surveyor's Michigan License No. 10705

