

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1554**

**L127800PA045**

\$ 13.00 MISCELLANEOUS RECORDING  
 28 DEC 94 8:19 A.M. RECEIPT# 129  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

Wayne  
 (County)

Located In:

Corner Code #

- |                                       |                            |             |
|---------------------------------------|----------------------------|-------------|
| 1. Public Land Survey                 | T <u>1</u> S R <u>10</u> E | <u>C-13</u> |
|                                       | T _____ R _____            | _____       |
|                                       | T _____ R _____            | _____       |
|                                       | T _____ R _____            | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____    | _____       |
|                                       | S _____ T _____ R _____    | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____    | _____       |
|                                       | S _____ T _____ R _____    | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                            |             |
| 5. Private Claims _____               |                            |             |

Compliance with  
**ACT 345, P.A. 1990**  
 APPROVED ON: 12-8-94 *JBF*  
**WAYNE COUNTY REMONUMENTATION**  
**MEER GROUP COMMITTEE**  
 Register of Deeds Stamp & File Number

**RC 1554**

I, William L. Roskelly in a field survey on November 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		8		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
C-13) SOUTH CORNER COMMON TO SECTIONS 31 AND 32, T.1 S., R.10 E.  
 G.L.O. (1830's) Joseph Fletcher set corner, witnesses B. Ash 10 N. 70 W. 10(gone) WO 20 N. 50 E. 22(gone).  
 W.P.A. (1930's) found a cross, witnesses: N.W. 36.82 base sign post (gone), S.W. 33.87 8" Oak(gone), S.E. 65.59 stop sign post(gone), E. 22.37 iron (not found), N.E. 49.55 4" Elm (gone)  
 No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-13) SOUTH CORNER COMMON TO SECTIONS 31 AND 32, T.1 S., R.10 E.  
 Found a steel bar in concrete monument in mon. box at the intersection of Joy and Beech Roads. Verified corner location by comparing W.P.A. data with field measurements:  
 C-13 to B-13 Record = 2610.49 Measured = 2611.14±  
 C-13 to C-12 Record = 2622.85 Measured = 2622.99  
 Angle line C-13 & B-13 to line C-13 & C-12 Record = 92° 36' 40" Measured = 92° 37' 17" ±  
 Angle line C-13 & C-12 to line C-13 & D-13 Record = 89° 49' 40" Measured = 89° 49' 17"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-13) SOUTH CORNER COMMON TO SECTIONS 31 AND 32, T.1 S., R.10 E.  
 Found a steel bar in concrete monument in mon. box at the intersection of Joy & Beech Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.  
 WITNESSES: Set nail & W.C.R. tag N.W. face P. pole N. 60° E. Dist. = 78.52  
 Found nail & W.C.R.C. tag S.E. face P. pole N. 60° E. Dist. = 78.70  
 Set nail & W.C.R. tag N.E. face P. Pole S. 60° E. Dist. = 85.92  
 Found P.K. nail & W.C.R.C. tag S.E. face P. pole S. 20° W. Dist. = 51.36  
 Set nail & W.C.R. tag East face P. pole S. 20° W. Dist. = 50.89  
 Found P.K. & W.C.R.C. tag S.W. face P. pole N. 50° W. Dist. = 59.27  
 Found mon. box conc. mon. steel bar due East Dist. = 22.50  
 Placed Wayne County Remonumentation brass marker and cap #10705

2R  
 110  
 MISC.

Signed by William L. Roskelly Date 12/27/94  
 Surveyor's Michigan License No. 10705

