

SURVEY & REMONUMENTATION

MAR 17 1998

Liber-29741 Page-2423.0
97331672LS 12/17/1997 12:06PM

FILE DO NOT MAIL SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne, Redford Twp.
(County)

Located in: DETROIT Corner Code #

- | | | |
|------------------------------------|-------------------------------------|----------------|
| 1. Public Land Survey | T <u> </u> S. R <u> </u> 10E | <u> </u> I-10 |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-9-97 *DP*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William L. Roskelly, in a field survey on Dec 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 East corner section 27, T.1 S., R.10 E., Redford Township
G.L.O. (1830's) Joseph Fletcher set corner, witnesses: B Ash 40N24W 13 (gone), Beech 10N82E 15 (gone).
W.P.A. (1930's) no witnesses. **\$7.00 DEED**

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #42670

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 East corner section 27, T.1 S., R.10 E., Redford Township
Set monument in mon. box at Evergreen road and railroad underpass (pavement).
Verified corner position by comparing City of Detroit Survey with field measurements:
Distance I-10 to I-9 Record = 2609.30' Measured = 2609.32' +/-
Distance I-10 to I-11 Record = 2627.94' Measured = 2627.81'
Angle line I-10 & I-9 to I-10 & I-11 Record = 179° 12' 49", Measured = 179° 13' 59" +/-
Plat of "Brightmoor - Evergreen Sub." compared to field measurements:
Distance I-10 to I-9 Record = 2609.30' Measured = 2609.66'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 East corner section 27, T.1 S., R.10 E., Redford Township
Set monument in mon. box at Evergreen road and railroad underpass (pavement).
The selected location is a careful and faithful re-establishment of the position of the original corner.
Witnesses: N. 03° 03' 02" W. 37.17' set nail and tag # 10705 on conc. wall, N. 07° 22' 59" E. 100.54' set nail and tag # 10705 W. face conc. pillar, S. 19° 07' 19" E. 42.19' set nail and tag #10705 on conc. wall, S. 43° 42' 03" W. 46.59' set nail and tag #10705 on conc. wall, N. 60° 30' 16" W. 82.19' set steel bar and trav. cap #10705, N. 17° 14' 22" W. 101.60' set nail and tag #10705 on conc. pillar.
Placed Wayne County Remonumentation brass marker and cap #10705.

\$4.00 REMONUMENTATION

Signed by William L. Roskelly
Surveyor's Michigan License No. 10705

Date 12-16-97

R-LCR-7-4R-1PG-11 *DP*