

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1557**

**LI27800PA048**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

\$ 13.00 MISCELLANEOUS RECORDING  
 28 DEC 94 8:19 A.M. RECEIPT# 128  
 RECORDED  
 FOREST E. YOUNGLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

For corners in

Wayne  
 (County)

Located In:

Corner Code #

- |                                       |                            |       |
|---------------------------------------|----------------------------|-------|
| 1. Public Land Survey                 | T <u>1</u> S R <u>10</u> E | I-13  |
|                                       | T _____ R _____            | _____ |
|                                       | T _____ R _____            | _____ |
|                                       | T _____ R _____            | _____ |
| 2. Property Controlling in Section    | S _____ T _____ R _____    | _____ |
|                                       | S _____ T _____ R _____    | _____ |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____    | _____ |
|                                       | S _____ T _____ R _____    | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                            |       |
| 5. Private Claims _____               |                            |       |

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 12-8-94 *DOJ*  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
**Register of Deeds Stamp & File Number**

**RC 1557**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William L. Roskelly in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 I-13) SOUTH CORNER COMMON TO SECTIONS 34 AND 35, T.1 S.,R.10 E.  
 G.L.O. (1830's) Joseph Fletcher set corner, witnesses Elm 10 N. 60 E. 8 (gone)  
 Lynn 6 S. 27 E. 4 (gone).  
 W.P.A. (1930's) no information found.  
 No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I-13) SOUTH CORNER COMMON TO SECTIONS 34 AND 35, T.1 S.,R.10 E.  
 Found an iron pipe in a concrete monument in mon. box at the intersection of Joy & Evergreen Roads  
 Verified corner location by comparing City of Detroit data with field measurements:  
 I-13 to J-13 Record = 2633.50 Measured = 2632.92  
 Angle line I-13 & I-12 to line I-13 & J-13 Record = 89° 23' 43" Measured = 89° 27' 20"  
 Also compared Hearne Brothers document to field measurements:  
 Set up for section line from I-13 to I-12,  
 Found iron pipe at N.W. corner Evergreen and Westfield Measured 60' to East & set P.K. nail.  
 Iron at house #9303 Hearne Bros. page 219. Found steel bar at S.E. corner Evergreen and Westfield Measured 43' to west & set P.K. nail. Iron at house #9276 Hearne Bros. page 218.

2R  
 11 D  
 MISC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-13) SOUTH CORNER COMMON TO SECTIONS 34 AND 35, T.1 S.,R.10 E.  
 Found an iron pipe in a concrete monument in mon. box at the intersection of Joy and Evergreen Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.  
 Set nail & W.C.R. tag N.W. face P. pole N. 43° E. Dist. = 53.44  
 Set nail & W.C.R. tag S.W. face P. pole S. 30° E. Dist. = 58.54  
 Set nail & W.C.R. tag S.E. face P. pole S. 50° W. Dist. = 50.59  
 Set nail & W.C.R. tag S.W. face P. pole N. 40° W. Dist. = 56.45  
 Placed Wayne County Remonumentation brass marker with cap #10705

Signed by William L. Roskelly

Date 12/27/94

Surveyor's Michigan License No. 10705

