

DEC 29 1998

SURVEY & REMONUMENTATION

Libar-30035

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 02 1999

SECTION

For corners in

Wayne, Redford Twp. (County)	Located in: Detroit	Corner Code #
1. Public Land Survey	T 1 S. R 10 E	J-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-16-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William L. Roskelly, in a field survey on Dec 11, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
J-9)South corner section 23, T.1 S., R.10 E., Redford Township, City of Detroit
G.L.O. (1830's) Joseph Fletcher set temporary corner, no witnesses.
W.P.A. (1930's) no witnesses.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9)South corner section 23, T.1 S., R.10 E., Redford Township, City of Detroit
Set iron in a monument box at Schoolcraft and Artesian Road (pavement).
The corner position was re-established using occupation and "Brightmoor Carlin Sub." L 51, P. 50.
Verified corner position by comparing City of Detroit Survey with field measurements:
Distance J-9 to K-9 Record = 2627.90' Measured = 2627.78'
Distance J-9 to I-9 Record = 2618.53' Measured = 2618.17'
Angle line J-9 & K-9 to J-9 & I-9 Record = 179° 57' 10", Measured = 179° 57' 14"

\$7.00 DEED
\$4.00 REMONUMENTATION
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #101860

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-9)South corner section 23, T.1 S., R.10 E., Redford Township, City of Detroit
Set iron in a monument box at Schoolcraft and Artesian Road (pavement).
The selected location is a careful and faithful re-establishment of the position of the original corner.
Witnesses: N55°-48'-01"E. 41.60' set nail and WCR tag NW. face power pole,
S62°-02'-39"E. 53.17' set nail and WCR tag N. face power pole,
S37°-26'-37"W. 68.20' found steel bar NE corner lot 339 "Brightmoor Carlin Sub, S58°-03'-30"W. 54.73' set nail and WCR tag N. face power pole, N60°-52'-36"W. 43.61' set nail and WCR tag SE. face power pole.

Placed Wayne County Remonumentation brass marker and cap #10705.

Signed by William L. Roskelly Date Dec 28, 1998
Surveyor's Michigan License No. 10705

R LCR 7 4R 1PG U DJF

984528563LS
12/29/1998 11:52AM