

REMONUMENTATION

MAR 17 1998

Liber-29741 Page-2438.0
973316BOLS 12/17/1997 12:09PM

FILE DO NOT MAIL

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne, Redford Twp.
(County)

Located In: DETROIT Corner Code #

1. Public Land Survey

T 1 S. R 10 E L-11
T R
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-9-97
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, William L. Roskelly, in a field survey on Dec 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													1
4	7			8			9			10			11
5													12
6	10			17			16			15			14
7													13
8													20
9													21
10													22
11													23
12													24
13													25
													26
													27
													28
													29
													30
													31
													32
													33
													34
													35
													36

A. Description of original monument and accessories and/or subsequent restoration:


L-11 South corner section 25, T.1 S., R.10 E., Redford Township
G.L.O. (1830's) Joseph Fletcher set corner post, witnesses: Elm 10 N37 E9 (gone), Lynn 9 E15 (gone).
W.P.A. (1930's) no witnesses.
No RC's or CS's found on file at Wayne County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 South corner section 25, T.1 S., R.10 E., Redford Township
Set a concrete monument in a monument box centerline of Plymouth and Asbury Park roads (pavement).
Verified corner location by comparing City of Detroit coordinate data with field measurements.
L-11 to K-11 Record = 2611.20' Measured = 2611.47'
L-11 to M-11 Record = 2606.90' Measured = 2606.53'
Angle line L-11 & K-11 to L-11 & M-11 Record = 180°-19'-26" Measured = 180°-19'-35"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 South corner section 25, T.1 S., R.10 E., Redford Township
Set a concrete monument in a monument box centerline of Plymouth and Asbury Park roads (pavement).
The selected location is a careful and faithful re-establishment of the position of the original corner.
WITNESSES: Set nail and WCR tag NW face power pole N. 38° E. 55.61', Set nail and WCR tag SW face power pole S.34° E. 58.69', Set nail and WCR tag NW face power pole S. 34° W. 53.31', Set nail and WCR tag SW face power pole N. 40° W. 60.91'.
Placed Wayne County Remonumentation brass marker and cap #10705.



Signed by William L. Roskelly
Surveyor's Michigan License No. 10705

Date 12-16-97

D-107-10705-201 DP-1