

SURVEY & REMONUMENTATION

RC 1560

L127800PA051

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 13.00 MISCELLANEOUS RECORDING
 Filing Requirement of Act 74, Mich. P.A. 1976 28 DEC 94 8:20 A.M. RECEIPT# 129

For corners in

Wayne

(County)

Located In:

Corner Code #/

- | | | | | | | |
|------------------------------------|---|----------|---|-----------|---|-----|
| 1. Public Land Survey | T | <u>1</u> | S | <u>10</u> | E | M-3 |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| 2. Property Controlling In Section | S | | T | | R | |
| | S | | T | | R | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | |
| | S | | T | | R | |

RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-8-94 *DRJ*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1560

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Roskelly in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3 SOUTHEAST CORNER SECTION 1, T.1 S., R.10 E.
 G.L.O. (1830's) Joseph Fletcher set corner witnesses: Cypress 9 N. 51 W. 25, Do 10 S. 44 W. 30
 W.P.A. (1930's) no witnesses found.
 No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 SOUTHEAST CORNER SECTION 1, T.1 S., R.10 E.
 Found a steel bar in concrete in a monument box at the intersection of 7 Mile & Greenfield Roads Verified corner location by comparing City of Detroit data with field measurements:
 M-3 to M-2 Record = 2635.77 Measured = 2637.49. Also found another monument 4.19 to the South.
 M-3 to L-3 Record = 2623.40 Measured = 2623.18
 M-3 to M-4 Record = 2640.77 Measured = 2641.57
 M-3 to B-3 (T.1 S.R.11 E.) Measured = 2689.67
 Angle line M-3 & M-2 to line M-3 & L-3 Record = 89°09'54" Measured = 89° 07' 37"
 Angle line M-3 & L-3 to line M-3 & M-4 Record = 90°43'40" Measured = 90° 43' 40"
 Angle line M-3 & M-4 to line M-3 & B-3 (T.1 S.R.11 E.) Measured = 90° 53' 31"
 Angle line M-3 & B-3 (T.1 S.R.11 E.) to line M-3 & M-2 Measured = 89° 15' 12"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 SOUTHEAST CORNER SECTION 1, T.1 S., R.10 E.
 Found a steel bar in concrete in a monument box at the intersection of 7 Mile & Greenfield Road. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
 WITNESSES: 1) Set W.C.R. tag & nail S.E. face P. pole N. 42° E. Dist. = 72.51
 2) Set W.C.R. tag & nail N.E. face P. pole S. 53° E. Dist. = 68.46
 3) Set W.C.R. tag & nail N.W. face P. pole S. 50° W. Dist. = 61.23
 4) Set W.C.R. tag & nail N.E. face P. pole N. 32° W. dist. = 76.38
 Placed Wayne County Remonumentation brass marker & cap #10705.

Signed by William L. Roskelly Date 12/27/94
 Surveyor's Michigan License No. 10705

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 27, 1991
 REVISED MAY 14, 1996

