

SURVEY & REMONUMENTATION

RC 1561

LI27800PA052

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Wayne  
(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 1 S R 10 E M-4  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-8-94 *W.L.R.*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

RC 1561

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William L. Roskelly in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
M-4) EAST CORNER SECITON 12, T.1 S.,R.10 E.

G.L.O. (1830's) Joseph Fletcher set corner post witnesses: Cypress 9N.39 W. 23, Do 9N. 67 E.11.  
W.P.A. (1930's) no witnesses found.  
No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

\$ 13.00 MISCELLANEOUS RECORDING  
28 DEC 94 8:20 A.M. RECEIPT# 120  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-4) EAST CORNER SECITON 12, T.1 S.,R.10 E.

Found an iron pipe in concrete monument in mon. box at the intersection of Greenfield and Curtis Roads. Verified corner location by comparing City of Detroit data with field measurements:  
M-4 to M-3 Record = 2640.77 Measured = 2641.57  
M-4 to M-5 Record = 2620.47 Measured = 2621.02  
Angle line M-4 & M-3 to line M-4 & M-5 Record = 180° 03' 20" Measured: 180° 03' 19"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-4) EAST CORNER SECITON 12, T.1 S.,R.10 E.

Found an iron pipe in concrete monument in mon. box at the intersection of Greenfield and Curtis Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. WITNESSES:  
Found P.K. & W.C.R. tag S.E. face P. pole N. 48° E. Dist. = 57.53  
Found P.K. & W.C.R. tag N.E. face P. pole S. 38° E. Dist. = 54.12  
Found P.K. & W.C.R. tag S.E. face P. pole S. 50° W. Dist. = 43.63  
Top bolt of hydrant N. 39° W. Dist. = 58.52  
Placed Wayne County Remonumentation brass marker and cap #10705

Z R  
110  
MISC

Signed by William L. Roskelly Date 12/27/94  
Surveyor's Michigan License No. 10705

