

SURVEY & REMONUMENTATION

RC 1564

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127800PA055

For corners in

Wayne <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>10 E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-94 *[Signature]*
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1564

I, William L. Roskelly, in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-6) EAST CORNER SECTION 13, T.1 S., R.10 E.

G.L.O. (1830's) Joseph Fletcher set corner post witnesses: Beech 12 N. 47 W. 4, Sug 10 N. 74 E. 24.
W.P.A. (1930's) no witnesses found.
No R.C.'s or C.S.'s found on file at Wayne County Register of Deeds

\$ 13.00 MISCELLANEOUS RECORDING
DEC 94 8:21 A.M. RECEIPT# 12R
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6) EAST CORNER SECTION 13, T.1 S., R.10 E.

Found an iron pipe in a concrete monument in mon. box at the intersection of Greenfield and Puritan Roads.
Verified corner location by comparing City of Detroit data with field measurements:
M-6 to M-5 Record = 2628.95 Measured = 2629.32
M-6 to M-7 Record = 2641.57 Measured = 2640.91
Angle line M-6 & M-5 to line M-6 & M-7 Record = 180° 07' 00" Measured = 180° 05' 57"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6) EAST CORNER SECTION 13, T.1 S., R.10 E.

Found an iron pipe in a concrete monument in mon. box at the intersection of Greenfield and Puritan Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. WITNESSES:
Set nail & W.C.R. tag N.W. face P. pole N. 50° E. Dist. = 51.09
Set nail & W.C.R. tag N.E. face P. pole S. 52° E. Dist. = 68.77
Set nail & W.C.R. tag S.E. face P. pole S. 50° W. Dist. = 50.88
Top bolt hydrant N. 33° W. Dist. = 58.61
Placed Wayne County Remonumentation brass marker and cap #10705

2 R
11 D
MISC

Signed by William L. Roskelly

Date 12/27/94

Surveyor's Michigan License No. 10705

