

SURVEY & REMONUMENTATION

RC 1563

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127800PA054

For corners in

| | | |
|---------------------------------------|----------------------------|---------------|
| <u>Wayne</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>1 S</u> R <u>10 E</u> | <u>M-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-94 *WJF*
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

RC 1563

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, William L. Roskelly in a field survey on November 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-7) EAST CORNER OF SECTION 24, T.1 S., R.10 E.
G.L.O. (1830's) Joseph Fletcher set corner post witnesses: Beech S. 73 W. 18.
W.P.A. (1930's) no witnesses found.
No R.C.'s or C.S.'s found on file at Wayne County Reg. of Deeds.

\$13.00 MISCELLANEOUS RECORDING
28 DEC 94 8:21 A.M. RECEIPT # 128
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-7) EAST CORNER OF SECTION 24, T.1 S., R.10 E.
Found an iron pipe in a monument box at the intersection of Greenfield and Lyndon Roads. Verified corner location by comparing City of Detroit data with field measurements:
M-8 to M-7 Record = 2638.59 Measured = 2638.18
M-3 to East R.O.W. of Winthrop Road from Hearne Brothers pages 116 & 117 Record = 358 Measured = 358

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-7) EAST CORNER OF SECTION 24, T.1 S., R.10 E.
Found an iron pipe in a monument box at the intersection of Greenfield and Lyndon Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. WITNESSES:
Set nail & W.C.R. tag S.E. face P. pole N. 72° E. Dist. = 52.87
Set nail & W.C.R. tag N.E. face P. pole S. 60° E. Dist. = 67.21
Set nail & W.C.R. tag N.W. face P. pole S. 60° W. Dist. = 54.28
Set nail & W.C.R. tag N.E. face P. pole N. 23° W. Dist. = 85.72
Placed Wayne County Remonumentation brass marker stamped with #10705.

2R
11 D
MISC

Signed by William L. Roskelly Date 12/27/94
Surveyor's Michigan License No. 10705

