

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1566

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 8:21 A.M. RECEIPT# 120

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

L127800PA057

For corners in

Wayne <small>(County)</small>	Located In:	Corner Code #
1 Public Land Survey	T <u>1</u> S R <u>10</u> E	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2 Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3 Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4 Lot No. _____, Recorded Plat _____		
5 Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-8-94
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1566

I, William L. Roskelly, in a field survey on November 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
M-12) EAST CORNER SECTION 36, T.1 S., R.10 E.
 G.L.O. (1830's) Joseph Fletcher set corner, witnesses: Hickory 12 S. 82 W., Sug. 16 N. 13.
 W.P.A. (1930's) No witnesses found.
 L.C.R.C. L. 24236, P. 881,882 R.C. #950 2/1/89 Grant Ward found monument box and could not remove top, intersection of Greenfield and Chicago roads; witnesses:
 S. 57° W. 62.54' PUNCH MARK.W.RIM of M.B.T. MH. (not found)
 N. 49° E. 50.33' SET 60d SPIKE & DISC. S.E. FACE OF POWERPOLE (measured 51.06)
 S. 50° E. 54.43' STEEL JACKETED MONUMENT (not found)
 N. 35° W. 59.49' SET 60d SPIKE & DISC. S.W. FACE OF POWERPOLE (Measured = 59.30)
 No C.S.'s found on file at Wayne County Reg. of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-12) EAST CORNER SECTION 36, T.1 S., R.10 E.
 Found a steel bar (flat top) in concrete in a mon. box at the intersection of Greenfield and Chicago Roads. Verified corner location by comparing City of Detroit data with field measurements.
 M-12 to M-11 Record = 2628.90 Measured = 2629.14
 M-12 to M-13 Record = 2638.55 Measured = 2639.03
 Angle line M-12 & M-11 to line M-12' & M-13 Record = 179° 55' 35" Measured = 179° 53' 19"
 L.C.R.C. L.24236, P. 881,882 R.C. #950 2/1/89 Grant Ward: N. 35° W. 59.49' Set 60d spike & disc. S.W. face of powerpole (Measured 59.30)
 N.49° E. 50.33 SET 60D SPIKE AND DISC. S.E. FACE OF POWER POLE (measured 51.06 from actual point) Mr. Ward was unable to open mon. box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-12) EAST CORNER SECTION 36, T.1 S., R.10 E.
 Found a steel bar (flat top) in concrete in a mon. box at the intersection of Greenfield and Chicago Roads. The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. WITNESSES:
 Found P.K. & tag Ward #22445 S.E. face P. pole N. 58° E. Dist. = 51.06;
 West bolt signal light pole S. 40° E. Dist. = 56.11
 Set nail & W.C.R. tag N.W. face P. pole S. 52° W. Dist. = 59.48
 Found P.K. & tag Ward #22445 S.W. face P. pole N. 30° W. Dist. = 59.30
 Placed Wayne County Remonumentation brass marker stamped with #10705.

Signed by William L. Roskelly Date 12/27/94
 Surveyor's Michigan License No. 10705

