

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**L127849PA-119**

For corners in

WAYNE

(County)

Located In:  
**CITY OF DETROIT**

*OTHER*  
 Corner Code #

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>15</u> R <u>11E</u> | <u>#007</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
- (SEQUENCE # 2)*
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims SW CORNER OF 1/4 SECTION 55, TEN THOUSAND ACRE TRACT  
WEST GRAND BOULEVARD AND ROSA PARKS.

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 1-24-95 *JPL*  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

95017909

I, STEVEN E. DUNN, in a field survey on DECEMBER 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

10	9	8	7	6	5	4	3	2	1
11	12	13	14	15	16	17	18	19	20
30	29	28	27	26	25	24	23	22	21
31	32	33	34	35	36	37	38	39	40
50	49	48	47	46	45	44	43	42	41
51	52	53	54	55	56	57	58	59	60

WOODWARD AVENUE

**TEN THOUSAND ACRE TRACTS**  
**CITY OF DETROIT**

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**GLO POST -NO ORIGINAL EVIDENCE FOUND**  
**TEN THOUSAND ACRE TRACTS SURVEYED BY JOSEPH FLETCHER IN 1816**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:



\* **THIS CERTIFICATE IS BEING RECORDED TO CORRECT PREVIOUSLY RECORDED L.C.R.C. IN LIBER 26992, PAGE 861, (W.C.R.)**

**RE-ESTABLISHED CORNER BY SPLITTING BACK OF CURB AND BACK OF WALK AND COMPARING WITH FOUND CONTROL POINTS. ALSO COMPARED DISTANCE FROM SOUTHWEST CORNER OF 1/4 SECTION 55, TEN THOUSAND ACRE TRACT TO NORTHWEST CORNER OF 1/4 SECTION 55, TEN THOUSAND ACRE TRACT, AS SHOWN ON CITY OF DETROIT CARTOGRAPHIC SURVEY MAPS.**

**FIELD MEASUREMENTS AND RECORDED DISTANCES**  
 NORTHWEST CORNER TO SOUTHWEST CORNER 2698.37' (M.) 2698.73' (R.)

\$ 13.00 MISCELLANEOUS RECORDING  
 24 JAN 95 1:02 P.M. RECEIPT# 44A

**PLACED WAYNE COUNTY REMONUMENTATION MARKER STAMPED #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.**

RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**SOUTHWEST CORNER OF 1/4 SECTION 55, TTAT**  
**1/2" x 18" IRON ROD WITH WAYNE COUNTY REMONUMENTATION MARKER STAMPED #28408 IN MONUMENT BOX.**

**WITNESSES**

- |          |        |  |
|----------|--------|--|
| N. 70°W. | 45.95' | PK NAIL AND W.C.R. WITNESS TAG IN ASPHALT AT ISLAND NOSE           |
| S. 19°W. | 46.80' | PK NAIL AND W.C.R. WITNESS TAG IN ASPHALT AT ISLAND NOSE           |
| N. 20°E. | 49.90' | PK NAIL AND W.C.R. WITNESS TAG IN CONCRETE BASE OF LIGHT POLE      |
| S. 70°E. | 47.54' | PK NAIL AND W.C.R. WITNESS TAG IN TOP CONCRETE CURB AT ISLAND NOSE |

*2 Remon  
 11 Misc  
 N.D.*

Signed by Steven E. Dunn Date Jan. 19, 1995  
 Surveyor's Michigan License No. 28408