

**FILE DO NOT MAIL** LAND-CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Liber-29744 Page-1015.0  
 Corner Code # 97335327LS 12/22/1997 10:11AM

WAYNE  
 (County)

Located In:  
 CITY OF DETROIT

1. Public Land Survey T 1S R 11E E-1  
 T R  
 T R  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 12-2-97 DPZ  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on NOVEMBER 24, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	18	17			16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30	29			28		27		26		25		
11													
12	31	32			33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY SEPTEMBER 1816 JOSEPH FLETCHER SET A POST

NO EVIDENCE OF ORIGINAL CORNER

PLATS

L.37 P.89 "WETHERBEE OAK GROVE SUBDIVISION"  
 L.42 P. 16 "GRAND PARK SUBDIVISION" 6-3-1920  
 L.31 P. 33 (O.C.R.) "WYOMING PARK SUB'N" 3-4-1924  
 L.32 P. 13 (O.C.R.) "FOREST GROVE SUB'N NO. 3" 5-6-1924

SURVEY &  
 REMONUMENTATION  
 MAR 17 1998  
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND OAKLAND COUNTY REMONUMENTATION CAP IN EXISTING MONUMENT BOX.  
 VERIFIED LOCATION CITY OF DETROIT FIELD NOTES AND WALK & CURB SPLITS.

\$7.00 DEED  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI  
 Receipt #43579  
 \$4.00 REMONUMENTATION

FIELD MEASURED AND RECORD DISTANCES

E-1 TO D-1 2634.48 (M) 2634.48 (CITY OF DETROIT) 40 CH. (GLO)  
 E-1 TO F-1 2635.72 (M) 2635.15 (CITY OF DETROIT) 40 CH. (GLO)  
 D-1/E-1/F-1 180°07'39" (M) 180°07'00" (CITY OF DETROIT)

VERIFIED THAT IS COMMON CORNER USING OAKLAND COUNTY REMONUMENTATION FORM

37.60(M) 37.63(R) W.C.R. TAG IN CONCRETE WALK  
 95.55(M) 95.82(R) O.C.R. TAG IN UTILITY POLE  
 44.30(M) 44.26(R) O.C.R. TAG IN UTILITY POLE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 NORTHEAST CORNER SECTION 4 (COMMON CORNER), T.1 S., R.11 E., WAYNE COUNTY

ALUMINUM OAKLAND COUNTY REMONUMENTATION CAP IN EXISTING MONUMENT BOX

WITNESSES

29°AZ. 78.48' PK W/ WAYNE COUNTY REMONUMENTATION WITNESS TAG IN CONC. WALK  
 132°AZ. 37.60' REMONUMENTATION WITNESS TAG IN CONC. WALK  
 330°AZ. 70.80' REMONUMENTATION WITNESS TAG IN CONC. WALK  
 38°AZ. 95.55' FOUND PK W/ O.C.R. WITNESS TAG IN NORTHWEST FACE UTILITY POLE  
 239°AZ. 44.30' FOUND PK W/ O.C.R. WITNESS TAG IN NORTHWEST FACE UTILITY POLE



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn  
 Surveyor's Michigan License No. 28408

Date Dec. 18, 1997