

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

4.00 REMONUMENTATION  
 7.00 DEED  
 23 DEC 96 10:26 A.M. REDEI A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER EDS  
 WAYNE COUNTY, MI

For corners in

WAYNE  
 (County)

Located In: CITY OF DETROIT Corner Code # \_\_\_\_\_

1. Public Land Survey T 1S R 11E Corner Code # E-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**LIBER 29356 PAGE 104**  
 Compliance with  
 ACT 345, P.A. 1990 *DBL*  
**APPROVED ON: DEC. 6, 1996**  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

I, MARTIN C. DUNN, in a field survey on OCTOBER 10, 19 96,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in  
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
 manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or  
 by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in  
 conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law;  
 established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY (DATED SEPT., 1816), JOSEPH FLETCHER SET A POST.  
 NO EVIDENCE OF ORIGINAL CORNER FOUND.

PLATS

L. 34 P. 25	BIRWOOD PARK	
L. 35 P. 24	GLENDALE COURTS SUBDIVISION	8-16-1916
L. 39 P. 96	B.E. TAYLOR DETROIT CITY SUB'N No.1	
L. 46 P. 98	JOHN M. WELCH JR'S WYOMING-SCHOOLCRAFT SUBDIVISION	9-27-1923

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RE-ESTABLISHED CORNER ALONG THE CENTERLINE OF WYOMING (66' WD.(ASPHALT)) USING FOUND PROPERTY CORNERS ALONG THE WEST LINE OF WYOMING AND WALK AND STREET SPLITS OF WYOMING WITH REFERENCE TO GLENDALE COURTS SUBDIVISION. VERIFIED LOCATION WITH OTHER FOUND PROPERTY CORNERS ALONG WYOMING AND USING WALK AND STREET SPLITS WITH REFERENCE TO THE ABOVE LISTED PLATS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 SOUTHWEST CORNER SECTION 21 T.1S., R.11E.

PLACED BRASS WAYNE COUNTY REMONUMENTATION WASHER AND PLASTIC CAP #30081 ON 1/2" x 18" IRON REBAR WITHIN A NEW MONUMENT BOX.

WITNESSES

N.17°E.	105.51'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN WEST FACE OF UTILITY POLE
S.71°E.	41.26'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN CONCRETE WALK
S.35°W.	41.45'	"X" IN STONE CURB
N.55°W.	35.19'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN CONCRETE WALK

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Martin C. Dunn

Date 12-23-96

Surveyor's Michigan License No. 30081

4R  
 70  
 20  
 0