

APR 05 1998 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

WAYNE

(County)

Located In:

GREENFIELD TWP
(NOW CITY OF DETROIT)

Corner Code #

1. Public Land Survey	T	1S	R	11E	E-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Compliance with ACT 345, P.A. 1990
APPROVED ON: DEC 5 1995 nca.
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		6		4		3		2		1		
3													
4	7		8		8		10		11		12		
5													
6	18		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEVEN E. DUNN, in a field survey on OCTOBER 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED 3, SEPT. 1816

PLATS

L. 43 P. 95	ROBERT OAKMAN LAND CO. "BONAPARTE BOULEVARD SUBDIVISION"	OCTOBER 17, 1921
L. 51 P. 15	ROBERT OAKMAN LAND CO. "BONAPARTE AVE. & OAKMAN HIGHWAY SUB"	OCTOBER 3, 1924
L. 52 P. 86	ROBERT OAKMAN LAND CO. "WYOMING-OHIO SUBDIVISION"	MARCH 3, 1925
L. 52 P. 87	"ELLIS SUBDIVISION"	MARCH 3, 1925

OCTOBER 17, 1921
OCTOBER 3, 1924
MARCH 3, 1925
MARCH 3, 1925

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 T.1S, R.11E. COMMON TO E-1 T.2S., R.11E.

NO EVIDENCE OF CORNER FOUND

RE-ESTABLISHED NORTH LINE OF JOY ROAD USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMAN'S LAND COMPANY SUB" L. 52 P. 86. RE-ESTABLISHED EAST LINE OF WYOMING USING FOUND IRONS WITH REFERENCE TO "ROBERT OAKMAN'S LAND COMPANY SUB" L. 43 P. 95. VERIFIED LOCATION WITH STONE CURB SPLITS AND SIDEWALK SPLITS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

E-13 TO E-12 2643.32' (M.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" ROD IN MONUMENT BOX.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 T.1S., R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

AZ. 316°	59.74'	SET PK NAIL AND W.C.R. TAG IN NORTHWEST FACE OF UTILITY POLE
AZ. 198°	82.18'	SET PK NAIL AND W.C.R. TAG IN SOUTHEAST FACE OF UTILITY POLE
AZ. 152°	60.09'	SET PK NAIL AND W.C.R. TAG IN EAST FACE OF UTILITY POLE
AZ. 140°	60.71'	SET PK NAIL AND W.C.R. TAG IN CONC. WALK

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408

95 DEC -8 PM 2:10 95263072 FORESTE. YOUNGBLOOF

4
7D
7D