

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDATION

FEB 28 2000

For corners in

SECTION

WAYNE
(County)

Located In: CITY OF DETROIT

Corner Code #

Liber-30836 Page-18
99590753 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

1. Public Land Survey		T <u>1S</u> , R <u>11E</u>	<u>F-1</u>
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-99 *DPZ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, STEPHEN R. JACOBI, in a field survey on, DECEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1817

PLATS:

L. 29, P.84 "GARDEN HOMES SUBD'N"
L. 42, P. 83 "ASKEW PARK SUB'N"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-1), NORTH 1/4 CORNER, SECTION 5, T. 1 S., R. 11 E., WAYNE COUNTY CORNER IS NOT COMMON TO F-13, T.1 N., R. 11 E., OAKLAND COUNTY

ESTABLISHED WOODINGHAM AND NORFOLK USING FOUND PROPERTY CORNERS. VERIFIED LOCATION USING CURB AND WALKS SPLITS. RE-ESTABLISHED 1/4 CORNER USING RECORD DISTANCE FROM NORFOLK, PARALLEL TO WOODINGHAM.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

F-1 TO E-1 2635.57'
F-1 TO G-1 2631.62'
ANGLE E-1/F-1/G-1 179°52'13"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-1), NORTH 1/4 CORNER, SECTION 6, T. 1 S., R. 11 E., WAYNE COUNTY, CORNER IS NOT COMMON TO F-13, T.1 N., R. 11 E., OAKLAND COUNTY PLACED ALUMINUM WAYNE COUNTY REMONUMENTATION CAP W/ #30081 ON 1/2"X18" REROD IN ASPHALT PAVEMENT.

WITNESSES

S.03°E. 17.36'	FOUND OAKLAND COUNTY WITNESS TAG IN EAST FACE OF POWER POLE.
N.27°E. 65.00'	FOUND OAKLAND COUNTY WITNESS TAG IN SOUTHEAST FACE 8" LOCUS.
N.58°W. 152.30'	SET PK NAIL WITH WAYNE COUNTY WITNESS TAG SE FACE OF UTILITY POLE.
S.57°W. 45.94'	SET PK NAIL WITH WAYNE COUNTY WITNESS TAG SW FACE OF UTILITY POLE.
S.53°E. 1.05'	FOUND OAKLAND COUNTY REMONUMENTATION CORNER IN MONUMENT BOX.

THE SELECTED LOCATION IS CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Stephen R. Jacobi Date 12-21-99

Surveyor's Michigan License No. 43057

R LCR 9 4R 1Pg A *DPZ*