

FILE DO NOT MAIL

RF

FEB 28 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

WAYNE (County) Located In: CITY OF DETROIT Corner Code # G-1
1. Public Land Survey T 1 S., R 11 E.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Liber-30836 Page-19
99590772 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds.

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-99
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. Cell G-1 is highlighted.

I, STEPHEN R. JACOBI, in a field survey on, DECEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1817

PLATS: L. 29, P.54 "WOODLAND SUBDIVISION" 9-17-1913
L. 42, P. 83 "CASPER J. LINGEMAN'S LIVERNOIS-EIGHT MILE SUBDIVISION" 9-8-1925

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-1), NORTHEAST CORNER, SECTION 4, T. 1 S., R. 11 E., WAYNE COUNTY CORNER IS NOT COMMON TO G-13, T.1 N., R. 11 E., OAKLAND COUNTY

ESTABLISHED ALLEY PARALLEL TO LIVERNOIS USING STONE CURBS. VERIFIED LIVERNOIS WITH CORNERS AND STONE CURBS ON BOTH SIDES. VERIFIED 8 MILE WITH PROPERTY CORNERS. RE-ESTABLISHED CORNER AT INTERSECTION.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:
G-1 to G-13 (OAKLAND COUNTY) 1.61'
G-1 to H-1 2625.91'
Angle G-13/G-1/H-1 180°00'00"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-1), NORTHEAST CORNER, SECTION 4, T. 1 S., R. 11 E., WAYNE COUNTY, CORNER IS NOT COMMON TO G-13, T.1 N., R. 11 E., OAKLAND COUNTY PLACED ALUMINUM WAYNE COUNTY REMONUMENTATION CAP W/ #30081 ON 1/2"X18" REROD IN ASPHALT PAVEMENT.

WITNESSES

N.20°E. 74.83' FOUND MAG NAIL WITH OAKLAND COUNTY WITNESS TAG #24598 IN WEST SIDE UTILITY POLE.
S.70°E. 67.78' FOUND MAG NAIL WITH OAKLAND COUNTY WITNESS TAG #24598 SW SIDE OF LIGHT POLE.
S.66°W. 69.50' FOUND MAG NAIL WITH OAKLAND COUNTY WITNESS TAG #24598 SE SIDE OF UTILITY POLE.
N.42°W. 89.55' FOUND MAG NAIL WITH OAKLAND COUNTY WITNESS TAG #24598 EAST SIDE OF UTILITY POLE.
WEST 1.61' FOUND OAKLAND COUNTY REMON CORNER IN MONUMENT BOX

THE SELECTED LOCATION IS CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 12-21-99
Surveyor's Michigan License No. 43057

R LCR 9 4 R 11 E. A. [Signature]