

LAND CORNER RECORDATION CERTIFICATE

APR 05 1996 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

COMMISSION

(County)

Located In:

Corner Code #

GREENFIELD TWP
(NOW CITY OF DETROIT)

1. Public Land Survey

T 1S R 11E

G-12

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *ncd.*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		6		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEVEN E. DUNN, in a field survey on OCTOBER 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT. 3, 1816

PLATS

L. 12 P. 79
L. 29 P. 80
L. 32 P. 75

LERCHEN'S ADDITION TO GREENFIELD VILLAGE
DAILY PARK SUBDIVISION
WORTHMOOR SUBDIVISION

MAY 11, 1889
NOVEMBER 6, 1913
AUGUST 21, 1915



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND.

HELD STONE CURBS ALONG CHICAGO TO ESTABLISH EAST AND WEST LINE. HELD FOUND IRONS ON EAST SIDE OF LIVERNOIS TO ESTABLISH NORTH AND SOUTH LINE. VERIFIED LOCATION WITH OTHER IRONS AND STONE CURBS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

G-12 TO G-13 2635.00' (M.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ. 90°	60.57'	SET PK NAIL W/ TAG IN CONC. WALK
AZ. 136°	81.40°	SET PK NAIL W/TAG IN CONC. WALK
AZ. 232°	61.55°	SET PK NAIL W/TAG IN CONC. WALK
AZ. 236°	89.14'	SET PK NAIL W/TAG IN SOUTHEAST FACE OF 18" MAPLE

4
73
110

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408

95263073

95 DEC -8 PM 2: 10