

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located In:
CITY OF DETROIT

Liber-29744 Page-1018.0
Corner Code # 97335330LS 12/22/1997 10:11AM

SURVEY & REMONUMENTATION

MAR 17 1998

SECTION Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-2-97
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

1. Public Land Survey T 1S R 11E I-1
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, STEVEN E. DUNN, in a field survey on NOVEMBER 24, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY SEPTEMBER 1916 JOSEPH FLETCHER SET A POST

NO EVIDENCE OF ORIGINAL CORNERS

PLATS

L. 8 P. 25 (O.C.R.) "BRUCEFIELDS SUB'N" 4-3-1913
L. 29 P. 83 "GERMAN'S MONTROSE PARK SUB'N" 11-13-1913
L. 11 P. 30 (O.C.R.) "FRANK GRIX SUB'N" 4-8-1916

\$4.00 REMONUMENTATION
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #43579
\$7.00 DEED

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
6													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ALUMINUM OAKLAND COUNTY REMON CAP IN EXISTING MONUMENT BOX.
"GERMAN'S MONTROSE PARK SUB'N" DOES NOT MAKE ANY REFERENCE TO THE SECTION CORNER.
VERIFIED LOCATION ADJACENT SECTION CORNERS AND FOUND IRONS ALONG 8 MILE.

FIELD MEASURED AND RECORD DISTANCES

I-1 TO I-12 (O.C.)	2670.25 (M)	2670.07(O.C.R. GRID DIST.)	2674.00(O.C. PLATS)	AZ.358°18'19"
I-1 TO H-1	2646.32(M)	2645.98(O.C.R. GRID DIST.)	2646.50(MDOT)	AZ.268°23'55"
I-1 TO J-1	2647.97(M)	2647.63(O.C.R. GRID DIST.)	2649.33(MDOT)	AZ.88°00'34"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 NORTHWEST CORNER SECTION 2 (COMMON CORNER) T.1S., R.11 E., WAYNE COUNTY
ALUMINUM OAKLAND COUNTY REMONUMENTATION MAKER IN EXISTING MONUMENT BOX

WITNESSES

82°AZ. 111.74'	SOUTHWEST CORNER OF CATCH BASIN
123°AZ. 80.51'	NORTHEAST CORNER OF BRICK BUILDING
231°AZ. 38.51'	FOUND CUT "X" IN TOP CENTER NUT OF HYDRANT
285°AZ. 48.17'	FOUND MAG PK NAIL W/ OAKLAND COUNTY REMON. TAG IN SOUTHEAST COR. CONC. & STEEL DIVIDER



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn
Surveyor's Michigan License No. 28408

Date Dec. 18, 1997