

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

WAYNE

(County)

Located In:
GREENFIELD TWP
(NOW CITY OF DETROIT)

Corner Code #

1. Public Land Survey	T 1S R 11E	L-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEVEN E. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 33 P. 81	CADILLAC HEIGHTS	JANUARY 24, 1916
L. 34 P. 8	WASHINGTON BLVD. SUBDIVISION	MARCH 14, 1916
L. 34 P. 62	SEVEN-OAKLAND SUBDIVISION	APRIL 12, 1916
L. 35 P. 18	SEVEN-OAKLAND SUBDIVISION No.1	MAY 11, 1916

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF ORIGINAL CORNER FOUND.
RE-ESTABLISHED CORNER USING CURB SPLITS.
VERIFIED LOCATION USING FOUND IRONS AND DISTANCE TIES TO ADJACENT SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

L-3 TO K-3 2632.98' (M.) 2632.77' (R.)
L-3 TO M-3 2632.58' (M.) 2632.28' (R.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ. 37°	41.15'	DETROIT CONTROL MONUMENT
AZ. 132°	33.97'	SET PK NAIL WITH TAG IN CONC. WALK
AZ. 205°	63.09'	SET PK NAIL W/W.C.R. TAG IN WEST FACE OF UTILITY POLE
AZ. 347°	58.53'	SET PK NAIL W/W.C.R. TAG IN CONC. WALK @ SOUTH FACE OF SQUARE GAS HAND HOLE

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408



95263077

95 DEC -8 PM 2:11
FOREST E. YOUNGBLOOD
REGISTERED PROFESSIONAL SURVEYOR

4
7D
72