

APR 05 1996
LAND CORNER RECORDATION CERTIFICATE
 COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:
GREENFIELD TWP
 (NOW CITY OF DETROIT)

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 1S | R | 11E | M-4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *TRCAL.*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1							
3													
4	7	8	8	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

- | | | |
|-------------|----------------------------|------------------|
| L. 29 P. 79 | OAKDALE SUBDIVISION | NOVEMBER 6, 1913 |
| L. 33 P. 81 | CADILLAC HEIGHTS | JANUARY 24, 1916 |
| L. 34 P. 10 | CADILLAC HEIGHTS NO. 2 | MARCH 7, 1916 |
| L. 35 P. 14 | LELAND HEIGHTS SUBDIVISION | MAY 9, 1916 |



95263080

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 T.1S, R.11E. COMMON TO A-4 T.1S, R.12E.

NO EVIDENCE OF CORNER FOUND.

RE-ESTABLISHED CORNER USING FOUND IRONS ALONG 17' ALLEY AND IRONS ALONG DEQUINDRE ROAD. VERIFIED LOCATION USING BACK OF CURB SPLITS AND DISTANCES TO ADJACENT SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

- M-4 TO M-3 2644.83' (M.) 2644.90' (R.)
 M-4 TO M-5 2635.36' (M.) 2637.65' (R.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

95 DEC -8 PM 2: 11
 FOREST E. YOUNGBLOOD
 REGISTERED OF DEEDS
 470 N.D.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

- | | | |
|----------|--------|--|
| AZ. 35° | 47.11' | DETROIT CONTROL MONUMENT IN WALK |
| AZ. 130° | 38.33' | SET PK NAIL WITH WITNESS TAG IN EAST FACE OF WALK @ BUS STOP |
| AZ. 200° | 48.72' | SET PK NAIL WITH WITNESS TAG IN CONC. CURB |
| AZ. 285° | 57.07' | FOUND PK NAIL IN SOUTH FACE OF UTILITY POLE |

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408