

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in APR 05 1996

WAYNE (County) **COMMISSION** Filed In: **GREENFIELD TWP (NOW CITY OF DETROIT)** Corner Code #

1. Public Land Survey T 1S R 11E M-5
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *MCB.*
 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	6	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	18	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	28	28	27	26	26							
11													
12	31	32	33	34	36	36							
13													

I, STEVEN E. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS
 L. 29 P. 79 OAKDALE SUBDIVISION NOVEMBER 6, 1913
 L. 35 P. 14 LELAND HEIGHTS SUBDIVISION MAY 9, 1916

PLAT OF SURVEY FOR RECORDATION
 L. 25363 P. 730 JAMES VANHAVERMAAT, #33988 JUNE 1, 1991



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 T.1S, R.11E. COMMON TO A-5 T.1S.,R.12E.

FOUND PK NAIL.

VERIFIED LOCATION USING FOUND IRONS, BACK OF CURB SPLITS, AND TIES TO ADJACENT SECTION CORNERS. VERIFIED WITNESSES OF PLAT OF SURVEY FOR RECORDATION L. 25363 P. 730.

FIELD MEASUREMENTS AND RECORDED DISTANCES
 M-5 TO M-4 2635.36' (M.) 2637.65' (R.)

FOUND WITNESS TIES
 L. 25363 P. 730 44.10' FOUND PK IN UTILITY POLE
 59.95' FOUND PK IN UTILITY POLE
 57.18' FOUND PK IN UTILITY POLE

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

95 DEC - 8 AM 2: 11
 FOREST E. YOUNGBLOOD
 REGISTERED DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ 36° 43.97' FOUND PK NAIL IN SOUTHEAST FACE OF UTILITY POLE
 AZ 160° 59.86' FOUND PK NAIL IN UTILITY POLE
 AZ 222° 42.82' FOUND PK NAIL AND TAG IN CONC. WALK
 AZ 338° 57.12' FOUND PK NAIL IN UTILITY POLE

4
 7 D
 712.

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn Date DECEMBER 5, 1995
 Surveyor's Michigan License No. 28408